

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

MAY 1 1998

(START CARD) # 101919

(1) OWNER:

Well Number

Name Ben Franklin - Lisa Marie Hopkins
Address 35674 SE Squaw Mt Rd
City Estacada State Orn Zip 97023

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☒ Yes ☐ No Depth of Completed Well 250 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	50	Cement	0	150	39 sacks
8"	50	150				
6"	150	250				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+2	151	250	☒	☐	☒	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner: 5"	130	250	160	☐	☒	☐	☐
				☐	☐	☐	☐

Final location of shoe(s) 151

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Saw

☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
150	250	1/8 x 8	75	5"	20	☐	☒
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☒ Bailor ☐ Air ☐ Flowing
☐ Artesian

Yield gal/min Drawdown Drill stem at Time

60 50' 8 hrs
42 80'

Temperature of water 56 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Clack Latitude _____ Longitude _____

Township 3 N or S Range 4 E or W. WM.

Section 22 NW 1/4 NE 1/4

Tax Lot 700 Lot _____ Block _____ Subdivision _____

Street Address of Well (or nearest address) 35674 SE Squaw Mt Rd Estacada Orn

(10) STATIC WATER LEVEL:

80 ft. below land surface.

Artesian pressure _____ lb. per square inch.

Date 4-16-98

(11) WATER BEARING ZONES:

Depth at which water was first found 205

From	To	Estimated Flow Rate	SWL
45	80	Self-off	12
205	250	60+	80

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Top Soil	0	1	
Clay Brown	1	28	
Boulders + Gravel	28	80	
Clay Gray	80	128	
Lava Rock Redlandium	128	140	
Lava Rock Green Soil	140	153	
Lava Rock Gray Soil	153	205	
Lava Rock Red	205	210	80'
Lava Rock Black	210	220	
Lava Rock Red	220	235	
Lava Rock Black	235	250	

RECEIVED

JUL 7 - 1998

WATER RESOURCES DEPT
SALEM, OREGON

Date started 3-24-98 Completed 4-16-98

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Thomas Youngberg WWC Number 1512 Date 5-10-98

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed W.A. Youngberg WWC Number 257 Date 5-10-98