

CLW
53477

JUL - 9 1998

WELL I.D.# 122670

STATE OF OREGON
WATER SUPPLY WELL REPORT WATER RESOURCES DEPT.
(as required by ORS 537.765) SALEM, OREGON

(START CARD) # 111438

(1) OWNER: Well Number _____
Name PARADISE TRAIL CAMP
Address 2700 SE HARRISON
City MILWAUKIE State OR Zip 97222

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 118 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	20'	CEMENT	0	20	20 SACKS
6"	20'	118'				

How was seal placed: Method A B C D E
 Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Casing/Liner	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing	6"	+30"	118'	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

(7) PERFORATIONS/SCREENS:
 Perforations Method HOLTE AIR
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
93'	113'	1/2 x 1"	360			<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min _____ Drawdown _____ Drill stem at _____ Time _____
60 _____ 90' _____ 2 hr.

Temperature of water 47° Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County CLACKAMAS Latitude _____ Longitude _____
Township 3S N or S Range 8E E or W. WM.
Section 15 SW 1/4 NW 1/4
Tax Lot NO TAX LOT Block _____ Subdivision _____
Street Address of Well (or nearest address) FOREST RD 39
MT. HOOD OR 4 MILES EAST RHODEDENDRON

(10) STATIC WATER LEVEL:
_____ ft. below land surface. Date 6-10-98
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 21'

From	To	Estimated Flow Rate	SWL
21	118'	60+ g.p.m.	18'

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
SAND, GRAVEL, COBBLES, BLDRS.	0		
LIGHT GREY/ VERY ANGULAR,			
CLEAN LOOSE CRSE. TEXT.			
PUMICE LIKE		59	
SAME AS ABOVE BUT WEATHERED	59		
BROWN AND RED'		74	
SAME AS 0-59'	74	81	
GRAVELY BOULDERS W/SAND /	81		
COURSE ANGULAR GREY &			
BROWN CLEAN LOOSE		118	

Westerberg Drilling, Inc.
36728 S. Kropf Rd.
Molalla, OR 97038
829-2526

Date started 6-9-98 Completed 6-10-98

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Daniel J. Stadel WWC Number 1487 Date 7-2-98

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Steven N. Stadel WWC Number 688 Date 7-2-98