

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the
STATE ENGINEER, SALEM 10, OREGON
within 30 days from the date
of well completion.

RECEIVED
JUL 2 1964
STATE ENGINEER
SALEM, OREGON

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

State Well No. 2/4-2

State Permit No. _____

(1) OWNER:

Name Mr. W. T. McCoy
Address Rt. 1, Box 258
Sandy, Oregon

(2) LOCATION OF WELL:

County Clackamas Driller's well number _____
1/4 1/4 Section 2 T. 2S R. 4E W.M.
Bearing and distance from section or subdivision corner _____

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
In abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 0 ft. to 339 ft. Gage 280
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used Star Perforator
Size of perforations 3/16 in. by 1 in.
200 perforations from 325 ft. to 335 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Cement
Depth of seal 150 ft. Was a packer used? yes
Diameter of well bore to bottom of seal in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☒ Yes ☐ No
Type of water? rotten Depth of strata 370-380
Method of sealing strata off cement

(10) WATER LEVELS:

Static level 302 ft. below land surface Date 6-15-64
Artesian pressure lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 45 gal./min. with 33 ft. drawdown after 7 hrs.
" " " "
" " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 8"
Depth drilled 425 ft. Depth of completed well 349 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top soil	0	1
Red clay	1	37
Boulders & clay	37	94
Gravel & clay & boulders	94	144
Boulder & gravel conglomerate	144	162
Boulder	162	168
Boulder	168	172
Coarse brown sand rock	172	255
Water 3 gpm	255	259
Yellow clay	259	272
Water 4 gpm	272	274
Hard blue clay & silt	274	324
Gravel - water 45 gpm	324	336
Blue clay & purple shale	336	370
Purple shale & fine sand	370	380
30 gpm rotten water	380	380
Blue shale	380	412
Blue clay	412	425

Work started 3-30 19 64 Completed 6-15 19 64
Date well drilling machine moved off of well 6-15-64 19

(13) PUMP:

Manufacturer's Name _____
Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Calvin C. Bram Well Drilling
(Person, firm or corporation) (Type or print)

Address 17120 S. E. Foster Rd., Portland

Drilling Machine Operator's License No. 18

[Signed] Calvin C. Bram
(Water Well Contractor)

Contractor's License No. 222 Date 7-12, 19 64