

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

APR 15 1986

WATER RESOURCES DEPT

PLEASE TYPE or PRINT IN INK

RECEIVED (CLAC 5437)

05437

8/15/88

(for official use only)

(1) OWNER: SALEM, OREGON

Name Chatelain's Nursery
Address 37071 S.E. Kelso Rd
City Boring, Oregon 97009 State

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL: (4) PROPOSED USE (check):

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☒ Thermal ☐ Withdrawal ☐ ReInjection ☐
Cable ☐ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED: Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
8" Diam. from 160 ft. to 160 ft. Gauge 2.50
6" Diam. from 140 ft. to 300 ft. Gauge 2.00/5

(6) LINER INSTALLED: Steel ☐ Plastic ☒
Threaded ☐ Welded ☒
6" Diam. from 140 ft. to 300 ft. Gauge 2.00/5

(7) PERFORATIONS: Perforated? ☐ Yes ☐ No
Size of perforations 8AW in. by 6" x 1/8 in.
600 perforations from 300 ft. to 200 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS: Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(9) WELL TESTS: Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Air test 100 gal./min. with drill stem at 280 ft. 4 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(10) CONSTRUCTION: Special standards: Yes ☐ No ☒
Well seal—Material used cement
Well sealed from land surface to 48 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Amount of sealing material 29 sacks ☒ pounds ☐
How was cement grout placed? poured through trimmy pipe
Was pump installed? Type HP Depth ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL by legal description:

County Clackamas 1/4 1/4 of Section 4 of
Township 15 Range 4E WM.
(Township is North or South) (Range is East or West)

Tax Lot Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address) Northeast corner of Kelso Rd and Highway 26

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 60 ft.
Static level 100 ft. below land surface. Date 5-1-86
Artesian pressure lbs. per square inch. Date

(12) WELL LOG: Diameter of well below casing 8"
Depth drilled 320 ft. Depth of completed well 300 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	1	
Yellow Clay	1	5	
Blue Clay	5	12	
Brown Clay	12	18	
Cement gravel & boulders	18	75	
Cemented gravel	75	100	
Brown Sandstone - soft	100	150	
Black Sandstone - hard	150	168	
Rock	168	175	
Hard - fine cemented gravels	175	269	100'
Coarse cemented gravel	269	300	100'
Lightly cemented gravel - (casing)	300	320	100'
Water Bearing	185	190	
	269	320	

Date work started 3-24-86 /completed 4-1-86
Date well drilling machine moved off of well 4-1-86

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date 4-1-86, 19 86

(bonded) Water Well Constructor Certification:

Bond 2541611 Issued by: SAFECO
(number) (Surety Company Name)
On behalf of Ted Pulliam Well Drilling
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Ted Pulliam
(Water Well Constructor)
(Dated) 4-1-86

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690