

(1) OWNER: Well No. L27745
Name TONY MELE
Address 32399 SE COMPTON ROAD
City BORING St OR Zip 97009

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 300 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
10	0	35	CEMENT	0	35	25 SACKS
7 5/8	35	300				

Seal placement method C

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
	6	+1	300	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 300' 5 1/2" TUBEX

(7) PERFORATIONS/SCREENS:

[] Perf. Method
[] Screens Type Material
From To Slot Size Number Diam. Tele/pipe Size Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
50		300	1 hr.
50		300	2 hr

Temperature of water 52F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:
County CLACK Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 33 SW 1/4 SW 1/4
Tax Lot 807 Lot Block Subdivision
Street Address of Well (or nearest Address)
32399 SE COMPTON ROAD BORING, OR 97009

(10) STATIC WATER LEVEL:

105 ft. below land surface. Date 05/31/99
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 20		Est Flow Rate	SWL
From	To		
20	25	10-15 GPM	13
290	300	50 GPM	105

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
BROWN CLAY	2	9	
BLUE CLAY & GRAVEL	9	21	
LIGHTLY CEMENTED GRAVEL & BOULDERS	21	28	13
LIGHTLY CEMENTED GRAVEL WITH CLAY SEAMS	28	290	
LIGHTLY CEMENTED MED GRAVEL	290	300	105

RECEIVED

JUN 4 1999

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 05/28/99

Completed 05/31/99

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed _____ WWC Number 616
Date 06/01/99