

STATE OF OREGON
WATER WELL REPORT
 (as required by ORS 537.785)

REC-CLAC 56571
 NOV 30 1992

WELL NO. 2 Log 1

(START CARD) # NONE

(1) **OWNER:** Well Number: _____
 Name TOM REARDON HANER, ROSS & SONS
 Address 10136 SE 282 RD
 City BOLLING O. State OR Zip 97009

(2) **TYPE OF WORK:**
 New Well Deepen Recondition Abandon

(3) **DRILL METHOD**
 Rotary Air Rotary Mud Cable
 Other _____

(4) **PROPOSED USE:**
 Domestic Community Industrial Irrigation
 Thermal Injection Other _____

(5) **BORE HOLE CONSTRUCTION:**
 Special Construction approval Yes No Depth of Completed Well 200 ft.
 Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10	0	35	CEMENT	0	35	25
6	35	200				

How was seal placed: Method A B C D E
 Other _____
 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel: _____

(6) **CASING/LINER:**

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
C	1	200	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Liner: _____

Final location of sheets: _____

(7) **PERFORATIONS/SCREENS:**

Perforations Method MILSKNIFE
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Telo/pipe size	Casing	Liner
177	198	1/8	88	1/4 X 2		<input checked="" type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>

(8) **WELL TESTS: Minimum testing time is 1 hour**
 Pump Bailer Air Flowing Artesian
 Yield gal/min 35 Drawdown 43 Drill stem at _____ Time 1 hr.

Temperature of water 53 Depth Artesian Flow Found _____
 Was a water analysis done? Yes By whom _____
 Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
 Depth of strata: _____

(9) **LOCATION OF WELL by legal description:**
 Township 15 Latitude _____ Longitude _____
 N or S. Range 4 E E or W. WM. _____
 Section 30 _____
 Tax Lot _____ Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) 10136 SE 282 RD BOLLING

(10) **STATIC WATER LEVEL:**
107 ft. below land surface. Date 4/1/81
 Artesian pressure _____ lb. per square inch. Date _____

(11) **WATER BEARING ZONES:**
 Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
175	200	50	107

(12) **WELL LOG:** Ground elevation _____

Material	From	To	SWL
TOP SOIL BA	0	2	
CLAY BA BROWN	2	28	
CLAY BLUE	28	87	
CLAY ORANGE	87	92	
ROCK SOFT RED	92	140	
CLAY RED GRAY	140	172	
CEMENTED GRAVEL	172	200	

RECEIVED RECEIVED
 JAN 16 2001 NOV 06 2000
 WATER RESOURCES DEPT. SALEM, OREGON
 THIS WELL WAS STARTED BY AL HARRINGTON (MAY) HE BROKE THE CASING AND LEFT THE WELL UNFINISHED
 Date started 4/1/81 Completed 5/1/81

(unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
 Signed Paul Bills WWC Number 877 Date 1/9/92

(bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment of work performed on this well during the construction dates reported above. This work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
 Signed Paul Bills WWC Number 579 Date 1/9/92