

CLAC 56644
 CLAC
 56644

Wallace Zielinski
 9740 South Hwy 211
 Canby, OR 97013

Well I.D. L30619

Start Card # 101542

Clackamas County Township: 5S Range: 1E Sec: 10 SE1/4, NE 1/4

(7) PERFORATIONS /SCREENS

From	To	Slot size	Diameter	Tele/pipe size	casing
+3'	179'2"		10"		yes
179'2"	184'5"	.080	10"	p.s.	
184'5"	201'2"		10"	pipe	yes
201'2"	213'5"	.080	10"	p.s.	
213'5"	215'8"		10"	pipe	yes
215'8"	219'11"	.080	10"	p.s.	
219'11"	230'2"		10"	pipe	yes
230'2"	238'5"	.080	10"	p.s.	
238'5"	248'6"		10"	pipe	yes
248'6"	267'9"	.080	10"	p.s.	
267'9"	286'9"		10"	pipe	yes
286'9"	292'	.080	10"	p.s.	
292'	297'5"		10"	pipe	yes

3" Gravel feed pipe +1' - 178'

(12) WELL LOG

Material	From	To	SWL
Topsoil	0	2'	
Clay, brown	2	18	
Gravel, clay brown	18	34	
Sand & Silt, brown	34	42	
Clay sandy, silt	42	49	
Gravel, clay gray & brown	49	62	
Gravel	62	71	30'
Clay brown, & gravel	71	77	
Sand, brown	77	82	
Sandy clay	82	93	30
Sand, gravel	93	97	30
Sandy clay brown	97	103	
Sand & clay brown	103	117	30
Short gravel layers & sandy clay	117	121	30
Clay brown	121	126	
Clay gray, sticky	126	134	
Clay blue & gray, sticky	134	146	

RECEIVED

JUN 01 2001

WATER RESOURCES DEPT.
 SALEM, OREGON

RECEIVED

APR 13 2001

WATER RESOURCES DEPT.
 SALEM, OREGON

Material	From	To	SWL
Continued			
Clay red-brown, sticky	146	159	
Clay red, brown, blue, sticky	159	166	
Clay gray, sticky	166	169	
Clay gray	169	179	
Clay gray, silty	179	180	
Sand fine, layers of clay	180	185	88
Clay gray, silty	185	191	
Clay blue-gray silty	191	200	
Clay gray silty-trace sand	200	202	
Sand black	202	208	88
Sand black & clay layers	208	214	88
Clay black	214	217	
Sand black	217	220	88
Clay black	220	229	
Clay gray sticky	229	231	
Sand blue, clay layers	231	239	88
Clay brown	239	249	
Sand black & clay layers	249	258	88
Clay brown silty	258	261	
Sand black & brown silty clay	261	268	88
Clay blue	268	273	
Clay blue & gray sticky	273	279	
Clay blue sticky	279	287	
Clay green sticky w/sand layers	287	292	88
Clay green sticky	292	295	
Clay gray silty	295	302	
Clay gray sticky	302	304	
Clay blue-green	304	316	
Clay gray sticky	316	318	
Claystone	318	325	88
Clay blue & green	325	332	
Clay gray soft	332	342	
Clay gray hard	342	351	
Clay gray silty	351	363	
Clay gray sticky	363	366	
Clay gray & black	366	374	
Clay blue sticky	374	381	
Clay gray sticky	381	385	
Clay gray sticky w/trace sand	385	389	
Clay gray & brown sticky	389	392	
Clay green sticky	392	399	
Clay brown & gray, sticky	399	401	

RECEIVED

JUN 01 2001

WATER RESOURCES DEPT.
SALEM, OREGON**RECEIVED**

APR 13 2001

WATER RESOURCES DEPT.
SALEM, OREGON