

CITY OF LAKE OSWEGO

by Schneider Drilling Co.

Start Card #138412 Label #L33795

<u>FM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	40	Clay, brown, soft
40	55	Claystone, grey, soft, weathered
55	64	Sandstone, brown, medium, weathered
64	67	Sandstone, brown & grey, fractured
67	71	Sandstone, grey, hard, fractured
71	78	Sandstone, grey, medium-hard, coarse, vesicular
78	108	Sandstone, grey, medium-hard, coarse
108	110	Basalt, grey & black, fractured
110	118	Basalt, grey-brown-green, soft, vesicular
118	135	Basalt, grey, hard, fractured
135	142	Basalt, red & grey, medium, vesicular
142	149	Basalt, grey, medium-hard
149	158	Basalt, grey & brown, medium, fractured, vesicular w/claystone, yellowish-brown
158	165	Basalt, grey, hard
165	168	Basalt, grey, & green, fractured
168	190	Basalt, grey, hard
190	257	Basalt, grey, medium-hard, fractured
257	267	Basalt, grey, medium-hard
267	272	Basalt, red & grey & brown, soft, vesicular, claystone, yellow & brownish
272	292	Basalt, red-grey-brown, soft, vesicular w/claystone, yellow-brown
292	300	Basalt, brown & grey, vesicular
300	308	Basalt, grey, medium
308	340	Basalt, grey, hard
340	343	Basalt, grey, fractured, brown
343	346	Basalt, red-brown-grey, vesicular w/some claystone, green
346	350	Basalt, red-brown-grey, vesicular
350	379	Basalt, grey, medium-hard, fractured
379	396	Basalt, grey, fractured, soft
396	423	Basalt, grey, hard, fractured
423	450	Basalt, grey, medium, fractured
450	469	Basalt, grey, hard, fractured
469	486	Basalt, black, medium, fractured, vesicular
486	516	Basalt, brown soft, vesicular
516	554	Basalt, grey, medium-hard, fractured
554	573	Basalt, black, medium-soft, fractured, vesicular
573	585	Basalt, grey, hard

RECEIVED

MAY 04 2001

WATER RESOURCES DEPT
SALEM, OREGON