

Clac 57896

State of Oregon

State Well ID L52955

WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

Start Card # 137726

(1) OWNER: Well No. L52955
 Name BECKER FAMILY TRUST
 Address PO BOX 422
 City ENTIAT St WA Zip 98822

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 520 ft
 Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
14	0	140	BENTONITE	0	8	8 SACKS
12	140	300	CEMENT	8	300	140 SACKS
10	300	520				

Seal placement method C & POURED IN

Backfill: from ___ ft to ___ ft Material
 Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	300	.250	STEEL	WELDED
Liner	8	280	520	.250	STEEL	WELDED

Final Location of shoe(s) 300' 9 1/2" TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIR KNIFE

[_] Screens Type Material
 Slot Tele/pipe
 From To Size Number Diam. Size Casing/liner
 420 520 1/8X2 1500 LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
300		520	1 hr.

Temperature of water 51F Depth Artesian Flow Found
 Was water analysis done? NO By whom
 Reason for water not suitable for use
 Depth of strata

(9) LOCATION OF WELL by legal description:

County CLACK Lat. ° ' " Long. ° ' "
 Township 1 S Range 4 E WM.
 Section 29 SW 1/4 NE 1/4
 Tax Lot N/A Lot Block Subdivision
 Street Address of Well (or nearest Address)
 SW CORNER WAYBILL & REVENUE ROAD BORING, OR 97009

(10) STATIC WATER LEVEL:

252 ft. below land surface. Date 06/07/02
 Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 90

From	To	Est Flow Rate	SWL
90	120	5+ GPM	70
360	515	300+ GPM	252

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
RED CLAY	2	56	
RED CLAY & GRAVEL	56	90	
LIGHTLY CEMENTED GRAVEL & BOULDERS	90	241	70
CEMENTED GRAVEL WITH SEAMS OF CLAY	241	360	
FINE BLACK CEMENTED GRAVEL	360	515	252
BLUE CLAY	515	520	

TED PULLIAM WELL DRILLING
 9480 S.E. 172nd
 Boring, Oregon 97009
 Phone 665-3353

Date started 05/29/02

Completed 06/07/02

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Ted Pulliam* WWC Number 616
 Date 06/07/02

MAY 05 2003