

OCT 02 2002

CLAC 58255

State of Oregon
WATER RESOURCES DEPT
SALEM, OREGON

WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L52962

Start Card # 140112

(1) OWNER: Well No. L52962
 Name VAN METER & SON NURSERY
 Address 10150 SE 352ND
 City BORING St OR Zip 97009

(2) TYPE OF WORK: DEEPEN

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 500 ft

Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
14	0	65	CEMENT	0	65	75 SACKS
12	65	260	CEMENT	200	260	35 SACKS
10	260	500				

Seal placement method C&SET PLUG&PUSH

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	260	.250	STEEL	WELDED
	8	0	330	.250	STEEL	WELDED

	Diam.	From	To	Gauge	Material	Connection
Liner	6	260	500	.250	STEEL	WELDED

Final Location of shoe(s) 260' 9.6"/330' 7.6" TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method TORCH

[_] Screens Type

Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
380	500	1/8X9	1000			LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type PUMP

Yield GPM	Draw-down	Drill stem at	Time
130	5		1 hr.
130	5		4 hr

Temperature of water 51F Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County CLACK Lat. ° ' " Long. ° ' "
 Township 1 S Range 4 E WM.
 Section 27 NE 1/4 NW 1/4
 Tax Lot 801 Lot Block Subdivision
 Street Address of Well (or nearest Address)
 8934 SE 352ND AVE BORING, OR 97009

(10) STATIC WATER LEVEL:

300 ft. below land surface. Date 09/28/02

Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

* Depth at which water was first found 40

From	To	Est Flow Rate	SWL
40	50	+5 GPM	40
360	500	100+ GPM	300

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
RED CLAY	2	10	
BROWN CLAY	10	30	
CLAY & GRAVEL & BOULDERS	30	50	
CEMENTED GRAVEL & BOULDERS	50	286	
FINE BROWN CEMENTED GRAVEL & SAND	286	440	300
FINE BROWN CEMENTED GRAVEL & SAND WITH	440		300
SEAMS OF BLUE CLAY		495	300
BLUE CLAY	495	500	

PULLED OUT 20 FEET OF 10" CASING AND
STARTED WELL OVER.

TED PULLIAM WELL DRILLING**9480 S.E. 172nd****Boring, Oregon 97009****Phone 665-3353**

Date started 09/20/02

Completed 09/28/02

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Ted Pulliam* WWC Number 616
 Date 09/28/02