

(1) OWNER: Well No. L60646
Name SALMON VALLEY WATER CO
Address 24525 E WELCHES ROAD
City WELCHES St OR Zip 97067

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: DOMESTIC&COMMTY

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO _____ Depth of Compl. Well 1140 ft
Explosives used NO _____ Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
14 0 70 CEM/BENT 0 7 14 SACKS
12 70 105 CEMENT 7 105 70 SACKS
6 105 1140
Seal placement method C&SET PLUG&PUSH
Backfill: from _____ ft to _____ ft Material _____
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Casing Diam. From To Gauge Material Connection
10 +1 105 .250 STEEL WELDED
Liner _____
Final Location of shoe(s) 105' 9 1/2" SHOE

(7) PERFORATIONS/SCREENS:
[] Perf. Method _____
[] Screens Type _____ Material _____
From To Slot Size Number Diam. Tele/pipe Size Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
1 _____ 1140 1 hr.
Temperature of water 52F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County CLACK Lat. ° ' " Long. ° ' "
Township 3 S Range 7 E WM.
Section 4 SE 1/4 NE 1/4
Tax Lot 900 Lot Block Subdivision
Street Address of Well (or nearest Address)
1/2 MILE S OF HWY 26/SALMON RIVER ROAD WELCHES, OR 97067

(10) STATIC WATER LEVEL:
36 ft. below land surface. Date 12/10/02
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 980
From To Est Flow Rate SWL
50 55 10-15 GPM 45
980 985 1 GPM 36

(12) WELL LOG:
Material Ground elevation From To SWL
SAND & BOULDERS 0 55 45
MEDIUM GRAY BASALTS 55 675
BLACK BASALTS WITH QUARTZ 675 680
MEDIUM GRAY BASALTS 680 970
SOFT GRAY & BROWN SHALE 970 1035 36
HARD BLACK BASALTS 1035 1140
*970'-1035' COULD CAVE IN WHEN HOLE
SATURATES FULL OF WATER.
SHOULD CASE TO 1040' WITH 8" PIPE.

RECEIVED
JAN 06 2003
WATER RESOURCES DEPT
SALEM OREGON

TED PULLIAM WELL DRILLING
9480 S.E. 172nd
Boring, Oregon 97009
Phone 605-3353
Date started 11/25/02 Completed 12/10/02

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *Ted Pulliam* WWC Number 616
Date 12/30/02