


(1) OWNER: Well No. L60641
 Name OREGON TRAIL SCHOOL DISTRICT 46
 Address 36520 SE PROCTOR ROAD
 City SANDY
 St OR Zip 97055

(9) LOCATION OF WELL by legal description:
 County CLACK Lat. ° ' " Long. ° ' "
 Township 1 S Range 4 E WM.
 Section 27 SW 1/4 NE 1/4
 Tax Lot 6000 Lot Block Subdivision
 Street Address of Well (or nearest Address)
 36520 SE PROCTOR ROAD SANDY, OR 97055

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC&COMMTY



(10) STATIC WATER LEVEL:
 304 ft. below land surface. Date 05/04/03
 Artesian pressure _____ lb per square in. Date _____

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO	Depth of Compl. Well	420 ft
Explosives used NO	Type	Amount
HOLE SEAL		
Diam.	From To	Material From To Amount
12	0 110	CEMENT 0 170 159 SACKS
10	110 170	
7 5/8	170 420	

(11) WATER BEARING ZONES:

Depth at which water was first found	50	360	Est Flow Rate	SWL
From To	50 60	360 420	10+ GPM	41
			50 GPM	304

Seal placement method C
 Backfill: from _____ ft to _____ ft Material _____
 Gravel: from _____ ft to _____ ft Size _____

(12) WELL LOG:

Material	Ground elevation	From To	SWL
TOP SOIL		0 2	
RED CLAY		2 40	
RED CLAY & GRAVEL		40 50	
LIGHTLY CEMENTED GRAVEL & BOULDERS		50 89	41
CEMENTED GRAVEL & LARGE BOULDERS		89 190	
CEMENTED GRAVEL		190 265	
FINE BLACK CEMENTED GRAVEL		265 337	
MULTI COLORED CEMENTED GRAVEL		337 360	
FINE BLACK CEMENTED SAND & GRAVEL		360 417	304
MEDIUM BLACK SAND		417 420	

(6) CASING/LINER:

Diam.	From To	Gauge	Material	Connection
Casing 6	+1 420	.250	STEEL	WELDED
Liner				

Final Location of shoe(s) 420' 5 1/2" TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIR KNIFE
 [_] Screens Type _____ Material _____

From To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
380 420	1/8X2	800			CASING

TED PULLIAM WELL DRILLING
 9480 S.E. 172nd
 Boring, Oregon 97009
 Phone 665-3353
 Date started 04/25/03 Completed 05/03/03

(8) WELL TESTS: Minimum testing time is 1 hour
 Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
50		400	1 hr.
50		400	4 hr.

Temperature of water 51F Depth Artesian Flow Found _____
 Was water analysis done? NO By whom _____
 Reason for water not suitable for use _____
 Depth of strata _____

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
 Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
 Signed *Ted Pulliam* WWC Number 616
 Date 05/04/03