

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

WATER RESOURCES DEPT
SALEM, OREGON

State Well No.

State Permit No.

25/4E-24cb

(1) OWNER:

Name DONALD TROXEL JR.

Address P.O. Box 561
Boring, Oregon 97009

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒ 250

6 5/8" Diam. from 0 ft. to 448 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in.	by	in.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.
perforations from	ft.	to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller

Yield: 50 gal./min. with 350 ft. drawdown after 1 hrs.

Baller test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 51 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement grout

Well sealed from land surface to 22 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 15 sacks

How was cement grout placed?

Pressure— from bottom of starter hole to land surface

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☒ Yes ☐ No

Type of water? sandy depth of strata 320

Method of sealing strata off driving casing

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 7919

NW 1/4 SW 1/4 Section 24 T. 2S R. 4E W.M.

Bearing and distance from section or subdivision corner

tax lot 1600

(11) WATER LEVEL: Completed well.

Depth at which water was first found 450 ft.

Static level 83 ft. below land surface. Date 7/24/79

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 457 ft. Depth of completed well 457 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil brown	0	1	
Gravel, sm. boulders	1	16	
Clay brown	16	22	
Cemented gravel	22	46	
Clay gray	46	265	
Claystone gray	265	272	
Claystone gray/sandstone streaks	272	275	
Clay gray/brown	275	278	
Sandstone brown	278	282	
Clay gray sandy	282	292	
Clay gray	292	315	
Clay gray/sand streaks	315	342	
Sandstone med	342	343	
Clay gray	343	422	
Clay gray/claystone	422	448	
Clay gray with sandstone streaks - water bearing	448	457	

Work started 7/18/79 19 Completed 7/24/79 19

Date well drilling machine moved off of well 7/24/79 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ricky L. Walcott Date 8/22/79, 19

(Drilling Machine Operator)

Drilling Machine Operator's License No. 1334

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Ross A. Jannsemm Well Drilling

(Person, firm or corporation)

(Type or print)

Address Rt. 1 Box 485 Estacada, Ore. 97023

[Signed] Ross A. Jannsemm

(Water Well Contractor)

Contractor's License No. 483 Date 8/22/79, 19

For Official Use Only:

Received Date:

9-24-02

County Well Log ID #

Clac 6172

Well Identification Tag #

I-61520

WELL IDENTIFICATION APPLICATION FORM

RECEIVED

RECEIVED

BUYER/CURRENT WELL OWNER:

SEP 24 2002

SEP 12 2002

WATER RESOURCES DEPT.
SALEM, OREGONWATER RESOURCES DEPT.
SALEM, OREGONName: Larry & Judy LedinMailing Address: 26612 SE Hwy 224City: Eagle Creek State: ORE Zip: 97022 Phone: ()**NOTE: Well Identification Tag will be sent to the above address unless otherwise specified.**

WELL LOCATION:

Latitude _____ Longitude _____

County: CLATSOP Owner's Well Number (1st or 2nd, etc) _____Township: 2 N or S, Range: 3 E or W, Section 24 1/4 _____ 1/4Tax Lot Number: 1600 Type of Well: water supply well monitoring _____

Address of Well (if different from above): _____

Does this well have a formal water right associated with it? Yes: _____ No: ✓

If Yes: Application #: _____ Permit #: _____ Certificate #: _____

WELL INFORMATION: (do not complete remainder of application if well log is attached)

well log
ATTACHED

Start Card Number: _____ Approx. Construction Date: _____

Well Constructor: _____

Name of Land Owner at Time of Construction: _____

Well Depth (in feet): _____ Static Water Level (in feet): _____

Diameter of Exposed Well Casing (in inches): _____

Please Return Completed Form to:

Well Identification Program
Oregon Water Resources Department
158 12th Street NE
Salem, OR 97301-4172

I-61520