

Wagnerberg Drilling, Inc.  
16726 S. Kropf Rd.  
Medalla, OR 97038

STATE OF OREGON  
WATER SUPPLY WELL REPORT  
(as required by ORS 537.765)

WELL I.D. # L ~~78678~~ LOST! Repl: L 145915

START CARD # 179786

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number \_\_\_\_\_  
Name Dave Sather  
Address 31150 S. Needy Rd.  
City Canby State OR Zip 97013

(2) TYPE OF WORK  New Well  
 Deepening  Alteration (repair/recondition)  Abandonment  Conversion

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  Auger  Cable Mud  
 Other \_\_\_\_\_

(4) PROPOSED USE  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION Special Construction:  Yes  No  
Depth of Completed Well 166 ft.  
Explosives used:  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

BORE HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds
10"	0	90	Cement	2	90	70 sacks
			Bentonite	0	2	2 sacks
6"	90	166				

How was seal placed: Method  A  B  C  D  E

Other Bentonite placed dry  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from 114 ft. to 166 ft. Size of gravel 8-12

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1'4"	133	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
riser 4"	113.5	134.5	CL200	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Liner: blank 4"	139.5	148	CL200	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
tail 4"	153	166	CL200	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Drive Shoe used  Inside  Outside  None  
Final location of shoe(s) 133'

(7) PERFORATIONS/SCREENS  
 Perforations Method \_\_\_\_\_  
 Screens Type V-wire Material stainless

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
134.5	139.5	.040		4"	PS	<input type="checkbox"/>	<input type="checkbox"/>
148	153	.040		4"	PS	<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
25	32'		1 hr.

Temperature of water 56 Depth Artesian Flow Found \_\_\_\_\_

Was a water analysis done?  Yes By whom \_\_\_\_\_

Did any strata contain water not suitable for intended use?  Yes  No

Salty  Muddy  Odor  Colored  Other \_\_\_\_\_

Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL (legal description)  
County Clackamas  
Tax Lot 1006 Lot \_\_\_\_\_  
Township 5 S Range 1 E WM  
Section 9 NW 1/4 NW 1/4

Lat \_\_\_\_\_ " or \_\_\_\_\_ (degrees or decimal)  
Long \_\_\_\_\_ " or \_\_\_\_\_ (degrees or decimal)

Street Address of Well (or nearest address) (no address yet) just E. of  
31150 S. Needy Rd. Canby, OR 97013

(10) STATIC WATER LEVEL  
56 ft. below land surface. Date 11-8-05  
\_\_\_\_\_ ft. below land surface. Date \_\_\_\_\_  
Artesian pressure \_\_\_\_\_ lb. per square inch Date \_\_\_\_\_

(11) WATER BEARING ZONES  
Depth at which water was first found 13'

From	To	Estimated Flow Rate	SWL
13	34	N/A	N/A
135	139	15 gpm	56'
148	153	25 gpm	56'

(12) WELL LOG Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil brown	0	2	
Clay brown	2	13	
Clay brown silty	13	27	
Silt blue sandy	27	34	
Clay grey sticky	34	41	
Clay grey w/ gravel	41	43	
Gravel w/ brown clay	43	53	
Clay brown w/ small gravel	53	61	
Sand brown silty cemented	61	77	
Gravel w/ brown clay	77	80	
Silt brown crumbly w/ gravel	80	96	
Clay blue sandy	96	103	
Clay grey	103	109	
Clay green w/ coarse sand	109	116	
Clay brown	116	126	

continued on page 2

Date Started 10-20-05 Completed 11-8-05

(unbonded) Water Well Constructor Certification  
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1768 Date 11-11-05

Signed [Signature]

(bonded) Water Well Constructor Certification  
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 668 Date 11-11-05

Signed [Signature]

RECEIVED  
NOV 15 2005  
WATER RESOURCES DEPT  
SALEM, OREGON





Oregon Water Resources Department  
 725 Summer Street NE, Suite A  
 Salem Oregon 97301  
 (503) 986-0900  
 www.oregon.gov/owrd

Application for  
**Well ID Number**

Replacement Tag

RECEIVED

JAN 31 2022

OWRD

*Do not complete if the well already has a Well Identification Number.*

**I. OWNER INFORMATION**

Current Owner Name (please print): David Sather

Mailing Address: 31240 S. Needy Rd.

City, State, Zip: Canby, OR 97043

Mail Well ID to:  SAME AS ABOVE  In Care Of (C/O)

Name & Address: \_\_\_\_\_

City, State, Zip: \_\_\_\_\_

**II. WELL LOCATION INFORMATION** (Please fill out as completely as possible)

Township: 5 South (North / South) Range: 1 East (East / West) Section: 9 NW 1/4 of the NW 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 1006 County Clackamas

GPS Coordinates: Lat 45 deg 9' 16.22" N, Long 122 deg 41' 48.76" W

Street Address of Well, City: 31240 S Needy Rd, Canby, OR 97043

If the property had a different street address in the past: \_\_\_\_\_

**III. GENERAL WELL INFORMATION** (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation

Date Well Constructed (or property built): 11-8-2005 Total Well Depth: 166 ft Casing Diameter: 6 inch

Owner at time the well was constructed (if known): Dave Sather Well Report # (if known): CLAC 61783

Other Information: Nearest address on log at the time was 31150 S. Needy Rd. Well ID # L 78670 LOST!

SUBMITTED BY (please print): Doann Hamilton @ Pacific Hydro-Geology Inc

PHONE: 503-349-6946 EMAIL &/or FAX: phgdmh@gmail.com

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301.  
 Or EMAIL the completed PDF form to: Ladeena.K.Ashley@oregon.gov, or FAX it to: (503) 986-0902.

*For Official Use Only by the Oregon Water Resources Department:*

Received Date:

1-31-22

Well Report Number:

CLAC 61783

Well Identification #:

L-145915