

CLAC 62439

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L68331
Start Card # 173967

(1) OWNER: Well No. L68331
Name CASCADE MEADOWS
Address 31215 SE WAYBILL
City BORING St OR Zip 97009

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 500 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
14	0	80	BENTONITE	0	50	40 SACKS
12	80	240	CEMENT	50	240	80 SACKS

Seal placement method SET PLUG&PUSHED

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	8	+1	240	.250	STEEL	WELDED
	6	+1	500	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 8.5@240', 5.5@500' TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIR KNIFE

[] Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
440	500	1/8X2	800	6		CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
160		500	1 hr.

Temperature of water 50F Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County CLACK Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 32 NW 1/4 NE 1/4
Tax Lot N/A Lot Block Subdivision
Street Address of Well (or nearest Address)
HALEY RD & ORIENT BORING, OR 97009

(10) STATIC WATER LEVEL:

184 ft. below land surface. Date 05/20/06

Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found	From	To	Est Flow Rate	SWL
440	440	500	200 GPM	184

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	3	
BROWN CLAY	3	18	
BROWN CLAY & GRAVEL	18	26	
LIGHTLY CEMENTED GRAVEL & LARGE BOULDERS	26	300	
CEMENTED GRAVEL & BOULDERS	300	500	184

TED PULLIAM WELL DRILLING
9480 S.E. 172nd
Boring, Oregon 97009
503-685-9353

Date started 05/04/06

Completed 05/20/06

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed _____ WWC Number 616
Date 06/17/06

ORIGINAL & FIRST COPY - WATER RESOURCES DEPARTMENT

SECOND COPY - CONSTRUCTOR

THIRD COPY - CUSTOMER

9809C 10/91

RECEIVED

JUN 20 2006

WATER RESOURCES DEPT
SALEM, OREGON