

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON

(START CARD) 28789

(1) OWNER:

Name Scott R. Winchester
Address 5616 S. E. Ten Eyck Rd.
City Sandy, State Or. Zip 97055

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 325 ft.

Explosives used ☐ ☒ Type Amount

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
10"	0 25	Bentonite	0 25	18 sacks	
		poured and tamped			
6"	25 518				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☐ Other bent. poured and tamped

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+ 1	174	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4"	+1	315	.250	☒	☐	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) 174 ft.

(7) PERFORATIONS/SCREENS:

☐ Perforations

Method

☒ Screens

Type Johnson

Material stainless steel

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
315	325	.006				☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump

☐ Bailer

☒ Air

☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
2gpm	complete		1 hr.

Temperature of water 52 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Clack Latitude Longitude
Township 2S N or S. Range 5E E or W. WM.
Section 7 1/4 1/4
Tax Lot 2201 Lot Block Subdivision
Street Address of Well (or nearest address) 40200 S.E.

Thomas Rd. Sandy, Oregon 97055

(10) STATIC WATER LEVEL:

294 ft. below land surface. Date 6-12-92

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 315

From	To	Estimated Flow Rate	SWL
315	325	2gpm	294

(12) WELL LOG:

Ground elevation 800

Material	From	To	SWL
Top soil	0	3	
Clay, brown, blders med	3	18	
clay, grey	18	32	
clay, blue	32	191	
clay, grey	191	206	
clay, blue	206	315	
clay, grey sandy water	315	329	294
clay, blue	329	372	
clay, grey some sand	372	398	
clay, blue	398	447	
clay, grey	447	472	
clay, blue	472	497	
rock, black hard	497	518	

placed concrete seal at bottom and
backfilled with drill cuttings from
325 to 518 feet

Date started 8-28-91 Completed 6-12-92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Estacada Well Drilling WWC Number 1459
Date 7-10-92