

**Westerberg Drilling, Inc.**  
**36728 S. Kropf Rd.**  
**Molalla, OR 97038**

STATE OF OREGON  
 WATER SUPPLY WELL REPORT  
 (as required by ORS 537.765)

WELL I.D. # L 84745

START CARD # 191074

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number  
 Name Rippling River Resort Golf, Inc.  
 Address 68010 E. Fairway Ave.  
 City Welches State OR Zip 97067

(2) TYPE OF WORK  New Well  
 Deepening  Alteration (repair/recondition)  Abandonment  Conversion

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  Auger  Cable Mud  
 Other

(4) PROPOSED USE  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other Test hole

(5) BORE HOLE CONSTRUCTION Special Construction:  Yes  No  
 Depth of Completed Well 216 ft.  
 Explosives used:  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

BORE HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds
10"	0	18	Bentonite	0	18	17 sacks
7"	18	216				

How was seal placed: Method  A  B  C  D  E  
 Other Bentonite placed dry  
 Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
 Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	216'10"	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: <u>None</u>				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used  Inside  Outside  None  
 Final location of shoe(s) 216'10" tubex shoe

(7) PERFORATIONS/SCREENS

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
85	N/A	216'	1 hr.
110	35'	pump	1 hr.

Temperature of water 49 Depth Artesian Flow Found \_\_\_\_\_  
 Was a water analysis done?  Yes By whom Coffey Labs  
 Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Color \_\_\_\_\_  
 Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL (legal description)  
 County Clackamas  
 Tax Lot 5700 Lot \_\_\_\_\_  
 Township 3 S Range 7 E WM  
 Section 5 SW 1/4 NE 1/4

Lat \_\_\_\_\_ ° \_\_\_\_\_ ' \_\_\_\_\_ " or \_\_\_\_\_ (degrees or decimal)  
 Long \_\_\_\_\_ ° \_\_\_\_\_ ' \_\_\_\_\_ " or \_\_\_\_\_ (degrees or decimal)  
 Street Address of Well (or nearest address) on golf course off of Fairway Ave.

(10) STATIC WATER LEVEL  
58 ft. below land surface. Date 4-6-07  
 \_\_\_\_\_ ft. below land surface. Date \_\_\_\_\_  
 Artesian pressure \_\_\_\_\_ lb. per square inch Date \_\_\_\_\_

(11) WATER BEARING ZONES

From	To	Estimated Flow Rate	SWL
9	54	30 gpm	9' est.
54	75	<10 gpm	16.5' est.
75	114	35 gpm	27.5' est.
153	216	250 gpm	58' est.

(12) WELL LOG

Material	From	To	SWL
Sand grey brown w/ boulders & cobbles angular	0	27	
Gravel w/ sand grey brown	27	35	
Sand w/ gravel	35	42	
Gravel w/ cobbles angular	42	45	
Boulder grey soft pumice	45	47	
Gravel packed angular red brown	47	54	
Boulder grey hard	54	56	
Gravel packed multi-colored	56	68	
Boulder grey dense	68	71	
Rubble grey angular basaltic	71	75	
Gravel w/ sand angular multi-clrd	75	86	
Cobbles & gravel coarse angular multi-colored	86	101	
Gravel weathered red brown cemented w/ sand	101	108	


Date Started 3-26-07 on page 2 Completed 4-6-07

(unbonded) Water Well Constructor Certification  
 I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1487 Date 4-11-07  
 Signed Daniel D. Stubb

(bonded) Water Well Constructor Certification  
 I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 688 Date 4-11-07  
 Signed Stewart N. Stubb



**CLAC 63420**



36728 S. Kropf Rd., Molalla, OR 97038 • Phone: (503) 829-2526 FAX (503) 829-7514

WELL ID#	OWNER/BUSINESS NAME	MAILING ADDRESS	CITY/STATE/ZIP
L84745	Rippling River Resort Golf, Inc.	68010 E. Fairway Ave.	Welches, OR 97067

WELL ADDRESS	COUNTY	TOWNSHIP	RANGE	SECTION	1/4	1/4	TAX LOT
on golf course off of Fairway Ave.	Clackamas	3S	7E	5	SW	NE	5700

(12) WELL LOG INFO. CONTINUED FROM PREVIOUS PAGE:			
MATERIAL	FROM	TO	SWL
Boulder grey dense	108	114	
Lava cinders red	114	125	
Gravel med w/ clay consolidated	125	128	
Boulder grey soft pumice	128	131	
Gravel med w/ clay consolidated	131	138	
Gravel med w/ some clay grey	138	141	
Gravel med w/ clay	141	144	
Boulder lava med grey	144	147	
Gravel med grey packed w/ wood	147	153	
Gravel med grey grn less angular than above	153	164	
Gravel med grey green w/ cobbles	164	166	
Gravel med grey green w/ coarse sand	166	182	
Gravel & cobbles med-coarse	182	184	
Gravel med-coarse grey green w/ sand crs	184	197	
Gravel med-coarse grey green w/ cobbles	197	200	
Gravel med semi cemented	200	206	
Cobbles & gravel crs w/ sand crs grey green	206	216	
Note:			
Owner is applying for a water right permit for this well. Upon receiving a permit, the 6" casing will be removed and a production well drilled in the same location.			
<b>Westerberg Drilling, Inc.</b>			
<b>36728 S. Kropf Rd.</b>			
<b>Molalla, OR 97038</b>			

**RECEIVED**

APR 23 2007