

CLAC 63486

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L88044
Start Card # 190964

(1) OWNER: Well No. L88044
Name Verna Jean Nursery, LLC
Address 8325 SE 327TH AVE
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 384 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
14	0	32	CEMENT	0	32	70 SACKS
12	32	217	CEMENT	145	217	20 SACKS
10	217	384				

Seal placement method C&SET PLUG&PUSH

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+2	217	.250	STEEL	WELDED
	8	0	384	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 217'10" & 384'8" TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIR KNIFE

Screens Type		Material				
From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
300	380	1/8X2	800	8"		CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
225		380	1 hr.

Temperature of water 53F Depth Artesian Flow Found ___
Was water analysis done? NO By whom ___
Reason for water not suitable for use ___
Depth of strata ___

(9) LOCATION OF WELL by legal description:

County CLACK Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 28 NW 1/4 NW 1/4
Tax Lot 1100 Lot Block Subdivision
Street Address of Well (or nearest Address)
327TH (ALTMAN ROAD) AVE GRESHAM, OR 97080

(10) STATIC WATER LEVEL:

206 ft. below land surface. Date 04/20/07
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 15		Est Flow Rate	SWL
From	To		
15	19	11 GPM	12
300	380	225 GPM	206

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
BROWN CLAY	2	8	
GRAVEL & BOULDERS	8	22	12
MULTI-COLORED CEMENT GRAVEL	22	87	
MULTI-COLORED LARGE GRAVEL	87	124	
MEDIUM MULTI-COLORED GRAVEL	124	182	
CEMENTED GRAVEL	182	284	206
BLACK & BROWN GRAVEL	284	384	

RECEIVED

MAY 15 2007

WATER RESOURCES DEPT
SALEM OREGON

Date started 04/03/07 Completed 04/20/07

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Dance Wagner WWC Number 1738
Date 05/14/07