

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Westerberg Drilling, Inc.
36728 S. Kropf Rd.
Molalla, OR 97038

WELL I.D. # L 87886START CARD # 191080

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Postlewait Farms Well Number _____
Name Postlewait Farms
Address 28923 S. Barlow Rd.
City Canby State OR Zip 97013

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 220 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
16"	0	220	Bentonite	0	16	48 sacks
			Cement	16	66	93 sacks

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☒ Other Bentonite placed dry

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 0 ft. to 220 ft. Size of gravel 8/12 & 6/9

(6) CASING/LINER

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	12"	+1	76	.250	☒	☐	☒	☐
	10"	+1.5	88	.250	☒	☐	☒	☐
	10"	98.5	108.5	.250	☒	☐	☒	☐
	10"	126	171	.250	☒	☐	☒	☐
Liner:	10"	188	196.5	.250	☒	☐	☒	☐
	10"	209	220	.250	☒	☐	☒	☐

Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 16" cut off @ 220'

(7) PERFORATIONS/SCREENS
☐ Perforations Method _____
☒ Screens Type V-wire Material stainless

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
88	98.5	.050		10"	PS	☐	☐
108.5	126	.050		10"	PS	☐	☐
171	188	.050		10"	PS	☐	☐
196.5	209	.060		10"	PS	☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
400	65'		1 hr.
400	87'		6 hr.

Temperature of water 53 Depth Artesian _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Yes ☐ No

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County Clackamas
Tax Lot 200 Lot _____
Township 5 S Range 1 E WM
Section 8 NW 1/4 NE 1/4
Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 7616 S. Sconce Rd.
Canby, OR 97013

(10) STATIC WATER LEVEL

58 ft. below land surface. Date 7-9-07
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 34'

From	To	Estimated Flow Rate	SWL
88	209	>400 gpm	58'

(12) WELL LOG

Material	From	To	SWL
Soil brown	0	1	
Silt brown	1	24	
Clay grey sticky	24	34	
Sandy clay grey	34	40	
Clay tan sticky	40	45	
Clay brown	45	55	
Clay w/ packed sand	55	68	
Packed silt brown w/ packed sand lenses	68	88	
Sand brown	88	92	
Brown sand & gravel	92	98	
Cemented gravel	98	103	
Packed silt blue	103	109	
Packed silt w/ sand blue grey	109	117	
Sand grey some gravel	117	126	

continued on page 2
Date Started 4-30-07 Completed 7-13-07

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 888 Date 8-1-07

Signed Steven M. Stadel

WATER RESOURCES DEPT

SALEM, OREGON

WELL ADDRESS	COUNTY	TOWNSHIP	RANGE	SECTION	1/4	1/4	TAX LOT
7616 S. Sconce Rd. Canby, OR 97013	Clackamas	5S	1E	8	NW	NE	200

MATERIAL	FROM	TO	SWL
Packed silt grey	126	132	
Clay grey & brown	132	150	
Claystone grey green soft	150	171	
Sand grey	171	176	
Claystone blue/grey	176	180	
Sand grey	180	187	
Packed silt w/ packed sand	187	198	
Sand grey	198	208	
Claystone grey	208	220	

10" well screen separated at the top of vertical rods where they are attached to weld ring @ 171'. A 4' piece of 10 gauge stainless steel tubing was swaged across this section to repair. Swaged sleeve from 169' - 173'. I.D. of sleeve is approx. 9-3/4".

Westerberg Drilling, Inc.
36728 S. Kropf Rd.
Molalla, OR 97038

AUG 03 2007

PAGE 2