

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

CLAC 64407
SKYLES DRILLING, INC.
503-656-2683

WELL ID # L 78473

START CARD # W193708

(1) OWNER: Well Number: 02
Name Robert & Carolyn Robbins
Address 11701 S. Carus Rd.
City Oregon City State OR Zip 97045

(2) TYPE OF WORK:
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 166 ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount	
Diameter	From	To	Material	From	To	sacks or pounds	
10	0	22	Bentonite	22	0	7 Sacks	
6	22	167					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 6 +2 157.5 .250 ☒ ☐ ☒ ☐
Liner: None ☐ ☐ ☐ ☐
Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 157.5

(7) PERFORATIONS/SCREENS:
Perforations Method
Screens Type
From To Slot size Number Diameter Tele/pipe size Casing Liner
None
RECEIVED
JAN 10 2008
WATER RESOURCES DEPT
SALEM, OREGON

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian
Yield gal/min Drawdown Drill stem at Time
15 166 1 hr.

Temperature of Water 59 Depth Artesian Flow found
Was a water analysis done? ☒ Yes By whom Driller 1.5ppm Iron
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County Clackamas Latitude Longitude
Township 3SOUTH N or S. Range 1EAST E or W. of WM.
Section 36A SW 1/4 NE 1/4
Tax lot 2200 Lot Block Subdivision
Street Address of Well (or nearest address) 11701 S. Carus Rd.,
Oregon City, OR

(10) STATIC WATER LEVEL:
90 ft. below land surface. Date 12/10/2007
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 93'

From	To	Estimated Flow Rate	SWL
93	95	5	90
162	166	15	90

(12) WELL LOG:

Material	From	To	SWL
Soil, brown	0	2	
Clay, brown, semi-silty	2	17	
Clay, tan, sandy @times	17	78	
Clay, gray	78	84	
Clay, brown & tan w/seams of sandstone, brown	84	93	
Sand, multicolored, coarse to medium	93	95	
Clay, tan	95	97	
Gravel, gray, medium to small	97	98	
Clay, gray	98	99	
Gravel, gray, medium to small	99	101	
Clay, gray-blue, gritty	101	118	
Clay, gray, sandy	118	139	
Clay, gray-blue	139	154	
Clay, gray, sandy	154	157	
Clay, gray	157	162	
Sand, m.c., semi-cemented	162	166	90
Clay, gray	166	167	
Filled in to 166'			

Skyles Drilling, Inc. (503) 656-2683
1169 Molalla Ave., Oregon City, OR 97045

Date started 12/5/2007 Completed 12/7/2007

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1601
Date 12/13/2007
Skyles Drilling, Inc.

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1592
Date 12/12/2007
Skyles Drilling, Inc.