

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

CLAC WATER WELL REPORT

06605

STATE OF OREGON JUN 4 1981

(Please type or print)

WATER RESOURCES DEPT

(Do not write above this line)

SALEM, OREGON

State Well No.

State Permit No.

254E-35 cc

(1) OWNER:

Name GERHARD A GANGSTAD
Address Route 2 Box 521
Gresham, Oregon 97030

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

6 5/8" Diam. from 0 ft. to 73 ft. Gage .250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 11 gal./min. with 22 ft. drawdown after 1 hrs.
" " " "
" " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 51 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement grout
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 8 sacks
How was cement grout placed? pressure grout from bottom of starter hole to land surface

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 7920
SW 1/4 SW 1/4 Section 35 T. 2S R. 4E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 116 ft.
Static level 78 ft. below land surface. Date 7/26/79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 120 ft. Depth of completed well 120 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil brown	0	1	
Clay brown sandy	1	8	
Cemented gravel	8	12	
Clay brown sticky	12	23	
Consolidated conglomerate	23	37	
Gravel med	37	46	
Consolidated conglomerate	46	65	
Rock gray brown med	65	82	
Consolidated conglomerate	82	115	
Gravel water bearing	115	120	

Work started 7/26/79 19 Completed 7/26/79 19
Date well drilling machine moved off of well 7/27/79 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ross A. Jannsen Date 8/12/79 19
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1334

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Ross A. Jannsen Well Drilling
(Person, firm or corporation) (Type or print)
Address Rt. 1 Box 485 Estacada, Ore. 97023

[Signed] Ross A. Jannsen
(Water Well Contractor)
Contractor's License No. 438 Date 8/12/79 19