

WATER WELL CONTRACTOR

Original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)
(Do not write above this line)

6664

State Well No. 215-2

CLAC

State Permit No.

(1) OWNER:

Name Harry Cholelain
Address RT 1 Box 236

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐
Cable ☒
Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

PIPING INSTALLED:

Threaded ☐ Welded ☒

" Diam. from 0 ft. to 3 3/4 ft. Gage 2.77
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

FORATIONS:

Perforated? ☒ Yes ☐ No.

perforator used Torch cut liner
Size of perforations 3/8 in. by 10 in.
150 perforations from 360 ft. to 390 ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Water level 302 ft. below land surface Date Nov. 67
_____ pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

120 gal./min. with 50 ft. drawdown after 6 hrs.

Ball test 40 gal./min. with 5 ft. drawdown after 2 hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION: Sand cement

Well seal—Material used Packfill clay & gravel

Depth of seal below 150 ft.

Diameter of well bore to bottom of seal 10 in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth _____

Was a drive shoe used? ☒ Yes ☐ No

Did any strata contain unusable water? ☒ Yes ☐ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County Clackamas Driller's well number _____
_____ 1/4 Section 2 T. 28 R. 5E W.M.

Bearing and distance from section or subdivision corner _____

(12) WELL LOG:

Diameter of well below casing to bottom

Depth drilled 400 ft. Depth of completed well 400 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	
red clay	2	21	
dark clay	21	28	
Top	28	52	
cobbles	52	61	
cement gravel	61	71	
boulders	71	73	
cement cobbles	73	78	
cement gravel	78	92	
clay red	92	95	
cement gravel	95	115	
river silt	115	155	
clay & gravel	155	184	
yellow sandstone	184	191	
loda rock blue clay	191	209	
seams			
blue clay	209	225	
brown clay	225	266	
yellow sandstone	266	281	
clay sandstone	281	297	
clay	297	320	
yellow sand	320	330	

Work started Oct 1967 Completed Nov 1967

Date well drilling machine moved off of well Nov 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] P. O. Olsen Date Dec, 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 2.14

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME P. O. Olsen (Type or print)

Address 18211 SE Powell Meridian

[Signed] P. O. Olsen (Water Well Contractor)

Contractor's License No. 282 Date Dec, 1967

Diameter of well below casing

Depth drilled

ft. Depth of completed well

北

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

[illegible]

Work started

19

Completed

18

ate well drilling machine moved off of well

19

25/5E-2

RECEIVED

APR 24 1985

WATER RESOURCES DEPT
SALEM, OREGON