

CLAC 66833

Rostorberg Drilling, Inc.

16728 S. Kropf Rd.

Canby, OR 97013

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 99814

START CARD # 201577

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER

Name **William & Sharyn Park**

Well Number _____

Address **24144 S. Skylane Drive**City **Canby**State **OR**Zip **97013**

(2) TYPE OF WORK

☒ New Well☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud☐ Other _____

(4) PROPOSED USE

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Construction: ☐ Yes ☒ NoDepth of Completed Well **265** ft.Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or Pounds
10	0	232	bentonite	0	20	71 sacks
6.25	232	240	cement	20	232	105 sacks
6	240	265				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E☒ Other **bentonite poured & probed**

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	+1	232	.250	☒	☐	☒	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner: none				☐	☐	☐	☐
				☐	☐	☐	☐

Drive Shoe used ☐ Inside ☒ Outside ☐ NoneFinal location of shoe(s) **232'**

(7) PERFORATIONS/SCREENS

☐ PerforationsMethod **none**☐ Screens

Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
none						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump☐ Bailer☒ Air☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
100	n/a	265	1 hr

Temperature of water **55** Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County **Clackamas**Tax Lot **302**

Lot _____

Township **4**

S

Range **1**

E

WM

Section **2**

NW

1/4

NE

1/4

Lat _____ " or _____ (degrees or decimal)

Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) _____

10694 Township Rd, Canby 97013

(10) STATIC WATER LEVEL

107.5 ft. below land surface. Date **5-10-10**

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found **25'**

From	To	Estimated Flow Rate	SWL
25	47	dnm	dnm
113	116	15	62'
237	265	100	107.5'

(12) WELL LOG

Ground Elevation _____

Material	From	To	SWL
soil	0	1	
silt brown	1	25	
silt blue	25	44	
cemented sand & gravel	44	47	
clay blue sticky	47	52	
silt blue with gravel	52	72	
silt grey with gravel	72	95	
clay grey with some wood	95	108	
claystone green	108	111	
clay grey with packed sand	111	113	
sand & gravel cemented	113	116	
clay green	116	121	
clay grey	121	125	
clay grey sticky	125	127	
clay blue sticky	127	130	
cont. page 2			

Date Started **5-3-10**Completed **5-10-10**

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number **1358**Date **5-12-10**

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number **688**Date **5-12-10**

Signed _____

MAY 13 2010

ORIGINAL - WATER RESOURCES DEPT
SALEM, OREGON

FIRST COPY - CONSTRUCTOR

SECOND COPY - CUSTOMER

06/16/2004

Testerberg Drilling, Inc.
6728 S. Kropf Rd.
Walla, OR 97036

WELL ADDRESS	COUNTY	TOWNSHIP	RANGE	SECTION	1/4	1/4	TAX LOT
10694 Township Rd, Canby 97013	Clack	4S	1E	2	NW	NE	302

[illegible]