

The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

RECEIVED

STATE OF OREGON
(Please type or print)

SEP - 5 1975 (Do not write above this line)

CLAC
6735

State Well No. 25/SE-8

State Permit No.

WATER RESOURCES DEPT.

(1) OWNER:

Name Michael Stewart SALEM, OREGONAddress 975 N.W. Angelina
Apartment 202

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☒ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 240 ft. Gage 255
5" Diam. from 232 ft. to 260 ft. Gage 255
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ NoType of perforator used Sandoyt

Size of perforations 1/16 in. by 1 in.
125 perforations from 232 ft. to 260 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 15 gal./min. with 30 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 53 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 200' ft.

Diameter of well bore to bottom of seal 8 in.

Diameter of well bore below seal 8 in.

Number of sacks of cement used in well seal 2 sacks

Number of sacks of bentonite used in well seal 1 sacks

Brand name of bentonite National

Number of pounds of bentonite per 100 gallons

of water mixed with clay slurry lbs./100 gals.Was a drive shoe used? ☐ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 8 mm

Gravel placed from 205 ft. to 260 ft.

(10) LOCATION OF WELL:

County Clark Driller's well number

1/4 1/4 Section 8 T. 25 R. 5E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 240 ft.

Static level 193 ft. below land surface. Date

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing to bottom

Depth drilled 260 ft. Depth of completed well 260 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	2	
sandy clay	2	4	
red clay	4	12	
red sticky clay	12	23	
yellow buff	23	67	
Red Volcanic tuffs	67	100	
semi-firm Rhododendron	100	152	
Rhododendron formation	152	260	193
8' clay -			
water bearing	240	260	193

Work started 6-9 1975 Completed 6-19 1975

Date well drilling machine moved off of well 6-19 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Donald H. Powell Date 6-7 1975

(Drilling Machine Operator)

Drilling Machine Operator's License No. 596

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Olsen Well Drilling Inc

(Person, firm or corporation) (Type or print)

Address 18211 SE Powell Ave[Signed] C. O. Olsen

(Water Well Contractor)

Contractor's License No. 272 Date 6-19 1975