

CLAC 67603

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 76462
START CARD # W206237

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name JAMES R. DIERKING
Address 20950 S. HARRIS ROAD
City Oregon City State OR. Zip 97045

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 160 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE SEAL
Diameter From To Material From To Sacks or pounds
12 0 8 Bedrock 0 8 9
12 8 50 Cement 8 50 2600 lbs
8 50 140 Casing _____
8 140 150 Casing Open
How was seal placed: Method ☒ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 8 +1 140 250 ☒ ☐ ☐ ☐
Liner: _____ ☐ ☐ ☐ ☐
Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 140'

(7) PERFORATIONS/SCREENS:
☒ Perforations Method Drive Down
☐ Screens Type _____ Material _____
From To Slot size Number Diameter Tele/pipe size Casing Liner
90 120 1/4" 1 220 8 ☒ ☐
_____ ☐ ☐
_____ ☐ ☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☒ Bailer ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time
24 18 _____ 1 hr.
_____ _____
_____ _____

Temperature of water 52 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Clatsop Latitude _____ Longitude _____
Township 2 N or S Range 3 E or W. WM.
Section 27 SW 1/4 NW 1/4
Tax Lot 1701 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 20950 S. HARRIS RD. Oregon City, OR.

(10) STATIC WATER LEVEL:
28 ft. below land surface. Date 2/28/11
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 95

From	To	Estimated Flow Rate	SWL
<u>95</u>	<u>110</u>	<u>30</u>	<u>28</u>

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
<u>CLAY/Lt. BROWN</u>	<u>0</u>	<u>2</u>	
<u>CLAY BROWN w/ small to large boulders</u>	<u>2</u>	<u>40</u>	
<u>Lt. BROWN sandstone</u>	<u>40</u>	<u>91</u>	
<u>Small to large GRAVEL</u>	<u>91</u>	<u>110</u>	<u>28</u>
<u>CLAY BROWN</u>	<u>110</u>	<u>150</u>	
RECEIVED			
MAR 04 2011			
WATER RESOURCES DEPT SALEM, OREGON			

Date started 11/4/10 Completed 2/3/11

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed Michael D. Smith WWC Number 1328 Date 3/3/11

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed Michael D. Smith WWC Number 1328 Date 3/3/11

CLAC 67603

20950 S. Harris Road
Oregon City, Oregon 97045



CLAC 67603 (UNRECORDED)

TL#1701, Part of the SW 1/4 of Sec 27,
and part of the SE 1/4 of Sec 28,
T2S,R3E of the Willamette Meridian.

RECEIVED

APR 18 2011

WATER RESOURCES DEPT
SALEM, OREGON

