

# CLAC 71578

State of Oregon  
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L07365  
Start Card # 92421

1) OWNER: Well No. L07365  
Name RON VAN METER  
Address 9835 SE 362ND  
City BORING St OR Zip 97009

2) TYPE OF WORK: DEEPEN

3) DRILL METHOD: ROTARY AIR

4) PROPOSED USE: DOMESTIC&IRRIGA

5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO \_\_\_\_\_ Depth of Compl. Well 480 ft  
Explosives used NO \_\_\_\_\_ Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL		
Diam.	From	To	Material	Amount
14	0	100	CEMENT	60 SACKS
12 5/8	100	260	CEMENT	30 SACKS
	260	480		

Seal placement method C

Backfill: from \_\_\_\_\_ ft to \_\_\_\_\_ ft Material \_\_\_\_\_

Gravel: from \_\_\_\_\_ ft to \_\_\_\_\_ ft Size \_\_\_\_\_

6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	260	.250	STEEL	WELDED

	Diam.	From	To	Gauge	Material	Connection
Liner	8	0	480	.250	STEEL	WELDED

Final Location of shoe(s) 260' 9 1/2/480' @ 1/2"

7) PERFORATIONS/SCREENS:

Perf. Method AIR KNIFE

Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
440	480	1/8x2	2000			CASING

8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
200		480	1 hr.

Temperature of water 52F Depth Artesian Flow Found \_\_\_\_\_

Was water analysis done? NO By whom \_\_\_\_\_

Reason for water not suitable for use \_\_\_\_\_

Depth of strata \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County CLACK Lat. ° ' " Long. ° ' "  
Township 1 S Range 4 E WM.  
Section 27 NE 1/4 SE 1/4  
Tax Lot 02501 Lot Block Subdivision  
Street Address of Well (or nearest Address)  
9835 SE 362ND AVE BORING, OR 97009

(10) STATIC WATER LEVEL:  
290 ft. below land surface. Date 09/04/96  
Artesian pressure \_\_\_\_\_ lb per square in. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found		Est Flow Rate	SWL
From	To		
320	480	200 GPM	290

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
RED CLAY	2	61	
CLAY & GRAVEL & BOULDERS	77	112	
BLACK ROCK	112	115	
CEMENTED GRAVEL	115	325	
FINE BLACK CEMENTED GRAVEL	325	395	290
COARSE CEMENTED GRAVEL	395	480	290

RECEIVED BY OWRD

AUG 14 2015

SALEM, OR

Date started 08/05/96 Completed 09/04/96

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed \_\_\_\_\_ WWC Number 616  
Date 09/04/96

*Ted Pulliam Well Drilling*  
503-665-3353

**CLAC 71578**

**TED PULLIAM WELL DRILLING INC**

**PO BOX 505**

**GRESHAM OR 97030**

**503-665-3353**

**WATER RESOURCES DEPT**

**WELL REPORT**

**RE: RON VAN METER VAN METER NURSERY**

**VAN METER NURSERY IS TRYING TO PERFECT THEIR WATER RIGHTS AND HAVE BEEN WORKING WITH  
A CERTIFIED WATER RIGHTS EXAMINER.**

**IT HAS COME TO THERE ATTENTION THAT WRD DOES NOT HAVE A COPY OF THEIR WELL REPORT.**

**HERE IS ONE OF OUR COPIES OF THE ORIGINAL WELL REPORT DRILLED IN SEPT 1996, DRILLED BY TED  
PULLIAM, LIC # 616.**



**TED PULLIAM WELL DRILLING INC.**

**RECEIVED BY OWRD**

**AUG 14 2015**

**SALEM, OR**