

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

CLAC 73228

SKYLES DRILLING, INC.

503-656-2683

WELL ID # L 124973

START CARD # W1034928

CLAC 73228

(1) OWNER:

Well Number: 01

Name Hidden Creek Polo Club

Address c/o Sean Tyler Keys, LLC, 7105 SW Varns St, #220

City Tigard State OR Zip 97223

(2) TYPE OF WORK:

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 182 ft.

Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount	
Diameter	From	To	Material	From	To	sacks or pounds	
10	0	118	Bentonite	118	0	51 Sacks	
6	118	186	Calculated			51 Sacks	

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Poured

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	+1.5	118	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4	4	182	Sch40	☐	☒	☐	☒
					☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Saw

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
161	181	1/8x3	72			☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min 100 Drawdown Drill stem at 180 Time 1 hr.

TDS Amount 103 ppm

Temperature of Water 59° Depth Artesian Flow found

Was a water analysis done? ☒ Yes By whom SDI, Iron 1.0 ppm

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Clackamas Latitude Longitude

Township 3SOUTH N or S. Range 1EAST E or W. of WM.

Section 08 NE 1/4 NE 1/4

Tax lot 00101 Lot Block Subdivision

Street Address of Well (or nearest address) 2882 SW Homesteader

Rd, West Linn, OR

(10) STATIC WATER LEVEL:

126 ft. below land surface.

Date 6/20/2017

Artesian pressure lb. per square inch.

Date

(11) WATER BEARING ZONES:

Depth at which water was first found 14'

From	To	Estimated Flow Rate	SWL
14	41	Trace	N/A
168	186	100	126

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Gravels	0	2	
Clay, brown	2	14	
Basalt, weathered	14	41	
Basalt, brown & red soft	41	52	
Basalt, gray & brown fractured	52	59	
Basalt, gray & black fractured	59	112	
Basalt, black	112	128	
Basalt, gray & brown	128	146	
Basalt, black & gray	146	168	
Basalt, gray & brown broken	168	182	126
Basalt, gray & brown w/seams of clay, loose caving	182	186	126

Bottom caved to 182'

SKYLES DRILLING, INC.

503-656-2683

RECEIVED BY OWRD
JUL 03, 2017

SALEM, OR

Date started 6/16/2017

Completed 6/20/2017

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed

Skyles Drilling, Inc.

WWC Number 1884

Date 6/22/2017

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed

Skyles Drilling, Inc.

WWC Number 1998

Date 6/22/2017