

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

CLAC 73956

SKYLES DRILLING, INC.

503-656-2693

WELL ID # L 129626

START CARD # W1038571

(1) OWNER: Well Number: 01
Name KT Enterprises, LLC
Address PO Box 1049
City Estacada State OR Zip 97023

(2) TYPE OF WORK:
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☒ Other Holte

(4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 58 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Amount	
Diameter	From	To	Material	From	To	sacks or pounds	
10	0	30	Bentonite	19	0	13 Sacks	
7.6	30	59	Calculated			8 Sacks	

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 30 ft. to 19 ft. Size of gravel 3/8Pea 12sks

(6) CASING/LINER:
Casing: Diameter 6 To +2 Gauge 57 Steel ☒ Plastic ☐ Welded ☒ Threaded ☐
Liner: None
Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
☐ Perforations Method _____
☐ Screens Type _____ Material _____
From To Slot size Number Diameter Tele/pipe size Casing Liner
None

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian
Yield gal/min Drawdown Drill stem at Time
42 55 1 hr.
TDS Amount 53 ppm

Temperature of Water 57.5° Depth Artesian Flow found _____
Was a water analysis done? ☒ Yes By whom SDI, Iron trace
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Clackamas Latitude _____ Longitude _____
Township 3SOUTH N or S. Range 3EAST E or W. of WM.
Section 14 NE 1/4 NE 1/4
Tax lot 33E11 Lot 01300 Block _____ Subdivision _____
Street Address of Well (or nearest address) 22877 S Stormer Rd,
Estacada, OR

(10) STATIC WATER LEVEL:
19 ft. below land surface. Date 5/2/2018
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 24'

From	To	Estimated Flow Rate	SWL
24	58	42	19

(12) WELL LOG:
Ground elevation _____

Material	From	To	SWL
Clay, brown	0	4	
Clay, brown gritty	4	9	
Lava, multicolored soft fractured	9	24	
Gravel, multicolored cemented	24	30	
Gravel, multicolored large to medium	30	36	
Conglomerate, multicolored	36	47	
Gravel & sand, multicolored cemented	47	58	19
Gravel, medium mixed w/clay, brown	58	59	
Filled in 1'			

SKYLES DRILLING, INC.
503-656-2693

Date started 5/1/2018 Completed 5/2/2018

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed SKYLES DRILLING, INC. WWC Number 1715
Date 5/3/2018

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed SKYLES DRILLING, INC. WWC Number 2006
Date 5/3/2018

RECEIVED

MAY 07 2018

OWNRD

Yield gal/min Drawdown Drill stem at Time
42 55 1 hr.

TDS Amount 53 ppm

Temperature of Water 57.5° Depth Artesian Flow found _____
Was a water analysis done? ☒ Yes By whom SDI, Iron trace
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____