

WATER WELL REPORT
STATE OF OREGON

CLAG 07733

RECEIVED

State Well No. 35/1W-56c

MAR 14 1984

State Permit No.

PLEASE TYPE OR PRINT IN INK

WATER RESOURCES DEPT

SALEM, OREGON

(1) OWNER:

Name WALTER KORB
Address 630 SE DIVISION ST
City SHERWOOD State OR

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal: Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

6" Diam. from 7.2 ft. to 40 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in by in

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.

" " " "

Air test 25 gal./min. with drill stem at 320 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 52° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement Grout

Well sealed from land surface to 38 ft.

Diameter of well bore to bottom of seal 10 3/4 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 10 sacks

How was cement grout placed? Pressure Grout

Was pump installed? No Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
SW 1/4 NW 1/4 Section 5 T. 3S R. 1W W.M.

Tax Lot # Lot Blk Subdivision

Address at well location: PARROT MT. Rd.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 296 ft.

Static level 184 ft. below land surface. Date 1-26-84

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 320 ft. Depth of completed well 320 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
BROWN SOIL	0	2	
BROWN CLAY	2	24	
HARD GRAY BASALT	24	56	
BROWN + GRAY BASALT	56	85	
HARD GRAY BASALT	85	102	
BROWN + GRAY BASALT	102	178	
HARD GRAY BASALT	178	204	
BROWN + GRAY BASALT	204	248	
HARD GRAY BASALT	248	296	
GRAY POROUS BASALT (water)	296	314	184
HARD GRAY BASALT	314	320	

Work started 1-24 1984 Completed 1-26 1984
Date well drilling machine moved off of well 1-27 1984

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Raymond A. Borchers Date 1-27, 1984

Bonded Water Well Constructor Certification:

Bond 378517 Issued by: New Hampshire
(number) Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Borchers Drilling, Inc.
(Person, firm or corporation) (Type of print)

Address Box 271A Sherwood

[Signed] Raymond A. Borchers

Water Well Constructor

Date 1-27, 1984

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690