

STATE OF OREGON
WATER SUPPLY WELL REPORT

CLAC 78814

WELL I.D. LABEL# L

151400

START CARD #

1075066

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/11/2024

(1) LAND OWNER

Owner Well I.D. _____

First Name JOHN & SANDY Last Name HOLM

Company _____

Address 9669 SE BULL RUN RDCity CORBETT State OR Zip 97019**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
 Material From To Amt sacks/lbs
 Seal: _____

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other _____
(4) PROPOSED USE
☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____
(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 76.00 ft.

BORE HOLE				SEAL			sacks/
Dia	From	To	Material	From	To	Amt	lbs
10	0	30	Bentonite Chips	0	2	16	S
7.38	30	76			Calculated	0.91	
			Cement with 3% Bento	2	30	756	P
					Calculated	569.6	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED TAMPED HYDR

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 8/27/2024 Begin Time 11 45**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	2	76	0.250	ST	☒		IN.	76
L	4		3.6	56	Sch40	PL		☒	IN.	

Temp casing ☒ Yes Dia 10 From + ☒ 1 To 9**(7) PERFORATIONS/SCREENS**Perforations Method push down perforatorScreens Type quiklok Material pvc

Perf/ Screen	Casing/ Liner	Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Casing	6	25	40	.25	1	195	
Screen	Liner	4	56	76	.32			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	40		76	2

Temperature 54 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 31 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County CLACKAMAS Twp 1.00 S N/S Range 5.00 E E/W WMSec 29 NE 1/4 of the SE 1/4 Tax Lot 2200

Tax Map Number _____ Lot _____

Lat _____ " or 45.45357966 DMS or DD

Long _____ " or -122.21090335 DMS or DD

☒ Street address of well ☐ Nearest address9669 SE BULL RUN RD, CORBETT, OR 97019**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	<u>8/27/2024</u>			<u>16</u>
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 25.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
<u>8/27/2024</u>	<u>25</u>	<u>40</u>	<u>40</u>			<u>16</u>

(11) WELL LOGGround Elevation 1056.04 FT

Material	From	To
TOP SOIL	0	1
BROWN CLAY W SOFT BROWN ROCK	1	9
MULTI COLORED ROCK W SEAMS OF BROWN	9	12
MULTI COLORED GRAVEL	12	15
MULTI COLORED ROCK W BROWN CLAY	15	28
RHODODENDRON ROCK	28	58
GREY BASALT	58	69
brown gritty clay	69	76

Construction

Begin Date 8/26/2024 Begin Time 09 00 End Date 8/27/2024**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2089 Date 9/11/2024Signed TYLER KYLE (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1771 Date 9/11/2024Signed GEORGE YOUNGBERG (E-filed)Drilling Company: YOUNGBERG PUMP & WELL DRILLING LLC 503-630-3

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CLAC 78814

9/11/2024

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.45357966 Datum: WGS84

Longitude: -122.21090335

Township/Range/Section/Quarter-Quarter Section:
WM1.00S5.00E29NESE

Address of Well:

9669 SE BULL RUN RD, CORBETT, OR 97019

Well Label: 151400

Printed: September 11, 2024

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

