

STATE OF OREGON
WATER SUPPLY WELL REPORT

CLAC 79942

WELL I.D. LABEL# L

156295

START CARD #

1081703

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/4/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name _____ Last Name _____

Company WILLAMETTE FARMS LLC

Address 31348 S HWY 170

City CANBY State OR Zip 97013

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
 Material From To Amt sacks/lbs
 Seal: _____

(3) DRILL METHOD☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other _____**(4) PROPOSED USE**☐ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☒ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____**(5) BORE HOLE CONSTRUCTION**Special Standard ☒ (Attach copy)

Depth of Completed Well 499.00 ft.

BORE HOLE				SEAL				sacks/
Dia	From	To	Material	From	To	Amt		lbs
16	0	112	Cement	0	112	142.5	S	
10	112	499			Calculated	78		
					Calculated			

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☐ Other: _____

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from 389 ft. to 499 ft. Material CSS Size 6/9

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 7/6/2026 Begin Time 12 30

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____

Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	10	☒	1.5	427.65	0.250	ST	☒		OUT.	497.8
L	6		389.3	429.62	0.250	ST	☒			
L	6		489.68	499	0.250	ST	☒			

Temp casing ☐ Yes Dia _____ From + _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type V-Wire Material Stainless Steel

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
		6	429.62	489.68	.075			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	250	58.9	294	6
Pump	480	86	294	1

Temperature 61 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 170 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County CLACKAMAS Twp 5.00 S N/S Range 1.00 E E/W WM

Sec 11 NW 1/4 of the SW 1/4 Tax Lot 702

Tax Map Number _____ Lot _____

Lat _____ " or 45.14755000 DMS or DD

Long _____ " or -122.65746000 DMS or DD

☒ Street address of well ☐ Nearest address

10140 S HWY 211, CANBY, OR 97013

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/9/2026			122.25
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 30.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
4/7/2026	30	48	5			18.75
4/7/2026	52	65	10			18.75
4/10/2026	152	168	10			89.58
4/13/2026	205	213	100			90
7/9/2026	429	487	600			122.25

(11) WELL LOG

Ground Elevation 263.66 FT

Material	From	To
Crushed Rock	0	2
Clay Brown	2	18
Clay Grey with Gravel	18	21
Cemented Gravel Grey	21	30
Cemented Gravel Brown	30	48
Cemented Gravel with Brown Clay	48	52
Cemented Gravel Grey & Brown	52	65
Cemented Gravel with Brown Clay	65	80
Packed Silt Tan with Gravel	80	88
Clay Brown	88	104
Clay Red/Brown	104	112
Clay Blue	112	122
Silt & Sand Grey	122	125
Packed Silt Grey	125	152
Cemented Sand Dark Grey Hard Driving	152	168
Packed Silt Grey	168	175
Clay Grey with Brown	175	190
Silty Sand Grey	190	193
Packed Silt Grey	193	195

Construction

Begin Date 4/6/2026 Begin Time 16 30 End Date 7/9/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2085 Date 8/4/2026

Signed WESTON STADELI (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1487 Date 8/4/2026

Signed DANIEL STADELI (E-filed)

Drilling Company: Westerberg Drilling, Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

The only purpose for the special standard was to allow for drill rig absence during well screen selection/construction & shipping delay. 10" drive shoe was cut off from 495.3' - 497.8'. 6" pipe size well screen is H/D with 5.75 ID

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CLAC 79942

8/4/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.14755000 Datum: WGS84

Longitude: -122.65746000

Township/Range/Section/Quarter-Quarter Section:

WM5.00S1.00E11NWSW

Address of Well:

10140 S HWY 211, CANBY, OR 97013

Well Label: 156295

Printed: July 17, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

