

STATE OF OREGON
WATER SUPPLY WELL REPORT

CLAC 79969

WELL I.D. LABEL# L

160467

START CARD #

1083048

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/25/2026

(1) LAND OWNER

Owner Well I.D. 02

First Name SCOTT

Last Name KLUSMANN

Company

Address 28775 SW PETES MOUNTAIN RD

City WEST LINN

State OR

Zip 97068

(2) TYPE OF WORK☒ New Well☐ Deepening☐ Conversion☐ Alteration (complete 2a & 10)☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other**(4) PROPOSED USE**☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)

Depth of Completed Well 597.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	475	Bentonite	0	1	1	S
6	475	597			Calculated	0.46	
			Cement with 5% Bento	1	475	108	S
					Calculated	90.84	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED BENTONITE

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 8/17/2026 Begin Time 10 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	6	☒	1.5	475	0.250	ST	☒			
L	4.5		3	585	Sch40	PL		☒		

Temp casing ☐ Yes Dia From + To**(7) PERFORATIONS/SCREENS**

Perforations Method Drill

Screens Type Factory Slot Material PVC

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	4.5	575	583	.5	0.5	60	Pipe size
Screen	Liner	4.5	583	595	.32			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	60		592	1
Air	50		560	0.3
Air	40		543	0.3

Temperature 60 °F Lab analysis ☒ Yes By SDI, Iron 1.5 ppmWater quality concerns? ☐ Yes (describe below) TDS amount 130 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County CLACKAMAS Twp 3.00 S N/S Range 1.00 E E/W WM

Sec 16 SE 1/4 of the NE 1/4 Tax Lot 300

Tax Map Number 31E16AD Lot

Lat ° ' " or 45.31219316 DMS or DD

Long ° ' " or -122.68242656 DMS or DD

☒ Street address of well ☐ Nearest address

28775 SW PETES MOUNTAIN RD, WEST LINN, OR

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/20/2026			451
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 530.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/20/2026	530	587	60			451

(11) WELL LOG

Ground Elevation 505.53 FT

Material	From	To
Topsoil	0	1
Clay, brown, gritty	1	4
Basalt, gray & brown, fractured, weathered	4	12
Basalt, dark gray, hard	12	18
Basalt, gray & light gray, hard	18	52
Basalt, gray, hard	52	95
Basalt, black, soft	95	97
Basalt, dark gray, fractured, porous	97	110
Basalt, gray & brown, fractured	110	150
Basalt, gray, fractured	150	155
Basalt, reddish brown, fractured, soft	155	170
Basalt, gray, fractured, soft	170	181
Basalt, gray & dark gray, fractured, broken	181	207
Basalt, multicolored browns, fractured	207	229
Basalt, dark gray, hard	229	260
Basalt, gray, hard	260	270
Basalt, black, hard	270	285
Basalt, gray, fractured	285	323
Basalt, dark gray & gray, hard	323	445

Construction

Begin Date 8/4/2026 Begin Time 11 00 End Date 8/20/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2003

Date 8/24/2026

Signed JAIME MUNOZ JR (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 2006

Date 8/25/2026

Signed CHRISTEN BLAND (E-filed)

Drilling Company: Skytes Drilling, Inc. (503)656-2683

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

Liner hung up 2' from bottom.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CLAC 79969

8/25/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.31219316 Datum: WGS84

Longitude: -122.68242656

Township/Range/Section/Quarter-Quarter Section:

WM3.00S1.00E16SENE

Address of Well:

28775 SW PETES MOUNTAIN RD, WEST LINN, OR

Well Label: 160467

Printed: August 25, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

