

**STATE OF OREGON
WATER SUPPLY WELL REPORT**

CLAC 79986

WELL I.D. LABEL# L

157224

START CARD #

1083338

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/28/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name LARRYLast Name CLAY

Company _____

Address 25050 S. PIKE AVE.City OREGON CITYState ORZip 97045**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other _____**(4) PROPOSED USE**☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)Depth of Completed Well 241.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	30	Bentonite Chips	0	2	2	S
6	30	241				Calculated	0.91
			Cement with 3% Bently	2	30	664	P
						Calculated	569.6

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED, PROBED

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 8/26/2026 Begin Time 15 30**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount _____

Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	2	241	0.250	ST	☒		OUT.	241
L	4.5		61	221	Sch40	PL		☒		

Temp casing ☒ Yes Dia 10 From + ☒ 1 To 19**(7) PERFORATIONS/SCREENS**Perforations Method push down perforatorScreens Type quiklok Material pvc

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Casing	6	217	228	.25	1	143	
Screen	Liner	4.5	221	241	.32			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	15		240	1.5

Temperature 60 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 75 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County CLACKAMAS Twp 4.00 S N/S Range 2.00 E E/W WMSec 10 NW 1/4 of the NE 1/4 Tax Lot 105

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 45.24396184 DMS or DD

Long _____ ° _____ ' _____ " or -122.54450577 DMS or DD

☒ Street address of well ☐ Nearest address25050 S. PIKE AVE., OREGON CITY, OR 97045**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/26/2026			180
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONES

Depth water was first found 217.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/26/2026	217	228	15			180

(11) WELL LOGGround Elevation 420.25 FT

Material	From	To
TOP SOIL	0	2
BROWN SAND	2	7
SANDY BROWN CLAY	7	29
BROWN SANDSTONE FRACTURED	29	41
SAND & GRAVEL	41	63
BROWN SANDSTONE W/ GRAVEL & CLAY SEAMS	63	70
BROWN CLAY GRITTY	70	112
BROWN SAND	112	120
BLUE / GRAY CLAY	120	141
GRAY SAND	141	154
GRAY CLAY SANDY	154	157
GRAY SAND	157	166
SAND & GRAVEL	166	181
GRAY CLAY GRITTY	181	217
COURSE SAND W/B	217	228
BROWN CLAY STICKY	228	231
GRAY CLAY SANDY	231	241

Construction

Begin Date 8/25/2026 Begin Time 09 45 End Date 8/26/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2089 Date 8/28/2026Signed TYLER KYLE (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1771 Date 8/28/2026Signed GEORGE YOUNGBERG (E-filed)Drilling Company: Youngberg Pump & Well Drilling LLC

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CLAC 79986

8/28/2026

Map of Hole

