

STATE OF OREGON
WATER SUPPLY WELL REPORT

CLAC 79989

WELL I.D. LABEL# L

Page 1 of 3

139612
START CARD # 1081960
ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/31/2026

(1) LAND OWNER

Owner Well I.D.

First Name CRISTINE Last Name GROCHOWSKY
Company
Address 38063 SE COUPLAND RD
City ESTACADA State OR Zip 97023

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 256.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	68	Bentonite Chips	0	24	30	S
8	68	170	Calculated			12	
6	170	260	Cement	24	68	23	S
			Calculated			23	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☐ Other:

Backfill placed from 68 ft. to 169 ft. Material CEMENT

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/2/2026 Begin Time 13 30

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe Location
C	6	☒	1.5	170	0.250	ST	☒		OUT. 170
L	4		136	256	Sdr 26	PL		☒	

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method Skil saw

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
		4	236	256	.125	8	36	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Bailer	15	10		1

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 45 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County CLACKAMAS Twp 3.00 S N/S Range 4.00 E E/W WM

Sec 24 SW 1/4 of the NW 1/4 Tax Lot 2002

Tax Map Number Lot

Lat ° ' " or 45.29700157 DMS or DD

Long ° ' " or -122.26877118 DMS or DD

☒ Street address of well ☐ Nearest address

38063 SE COUPLAND RD, ESTACADA, OR 97023

PROPERTY LOCATED AT END OF D

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/3/2026			222
Flowing Artesian?			Dry Hole?	

WATER BEARING ZONES

Depth water was first found 251.00

SWL Date From To Est Flow SWL (psi) + SWL (ft)

7/3/2026	251	256	15		222
----------	-----	-----	----	--	-----

(11) WELL LOG

Ground Elevation 1097.31 FT

Material	From	To
Soil brown	0	1
Clay brown	1	28
Clay red	28	37
Clay brown gritty	37	56
Rock grey med soft	56	120
Rock grey with red med	120	156
Rock grey soft with hard seams	156	249
Sandstone grey water bearing	249	260

Construction

Begin Date 5/1/2026 Begin Time 08 00 End Date 7/3/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 792 Date 8/31/2026

Signed RICK WALLAERT (E-filed)

Drilling Company:

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

--

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CLAC 79989

8/31/2026

Map of Hole

