

Amd 10/13/2026
STATE OF OREGON
WATER SUPPLY WELL REPORT

CLAC 80045

WELL I.D. LABEL# L

Page 1 of 2

START CARD #

ORIGINAL LOG #

157228

1083566

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

10/6/2026

(1) LAND OWNER

Owner Well I.D.

First Name JOHN

Last Name SPURGEON

Company

Address 28637 S. COX RD

City COLTON

State OR

Zip 97017

(2) TYPE OF WORK

☒ New Well

☐ Deepening

☐ Conversion

☐ Alteration (complete 2a & 10)

☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic

☐ Irrigation

☐ Community

☐ Industrial/ Commercial

☐ Livestock

☐ Dewatering

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 240.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
10	0	90	Bentonite Chips	0	6	5	S
6	90	240	Calculated			2.74	
			Cement with 3% Bento	6	90	2538	P
			Calculated			1708.8	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED PROBED HYD

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 9/17/2026 Begin Time 13 30

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 2 240	0.250	ST	☒		OTH.	90
L	4	☐ 20 220	Sch40	PL				

Temp casing ☒ Yes Dia 10 From + ☒ 3 To 22

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Quiklok Material pvc

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	4	220	240	.32			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	37.5		240	2

Temperature 59 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 81 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County CLACKAMAS Twp 4.00 S N/S Range 4.00 E E/W WM

Sec 30 NE 1/4 of the SW 1/4 Tax Lot 1601

Tax Map Number Lot

Lat ° ' " or 45.19102112 DMS or DD

Long ° ' " or -122.36495434 DMS or DD

☒ Street address of well ☐ Nearest address

28655 S COX RD

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	9/17/2026			174
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONES

Depth water was first found 223.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
9/17/2026	223	240	37.5			174

(11) WELL LOG

Ground Elevation 1194.88 FT

Material	From	To
top soil	0	3
multi colored rotten rock	3	31
soft gray rock	31	49
brown sticky clay	49	63
multi colored large gravel cemented	63	73
brown soft rock w pumice	73	181
multi colored rock	181	187
gray basalt hard	187	209
multi colored rock med/hard	209	216
red lava rock	216	223
gray basalt	223	240

Construction

Begin Date 9/16/2026 Begin Time 08 00 End Date 9/17/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2089 Date 10/6/2026

Signed TYLER KYLE (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1771 Date 10/6/2026

Signed GEORGE YOUNGBERG (E-filed)

Drilling Company: Youngberg Pump & Well Drilling LLC ph 503-630-3970

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

CLAC 80045

10/6/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.19102112 Datum: WGS84

Longitude: -122.36495434

Township/Range/Section/Quarter-Quarter Section:

WM4.00S4.00E30NESW

Address of Well:

28655 S COX RD

Well Label: 157228

Printed: October 6, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

