

# NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

CLAC  
WATER WELL REPORT (8039)  
OCT 10 1964  
STATE OF OREGON  
(Please type or print)

State Well No. 3/1W-11  
State Permit No.

## (1) OWNER:

Name Sam L. Amato  
Address Rt 2 Box 77A  
Sherwood Oregon

## (2) LOCATION OF WELL:

County Washington Driller's well number  
1/4 1/4 Section 33 T. 11 R. 1 W.M.  
Bearing and distance from section or subdivision corner

## (3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐  
Abandonment, describe material and procedure in Item 12.

## (4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐  
Irrigation ☐ Test Well ☐ Other ☐

## (5) TYPE OF WELL:

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Dug ☐ Bored ☐

## (6) CASING INSTALLED:

Threaded ☒ Welded ☐

6" Diam. from 0 ft. to 203 ft. Gage 250  
" Diam. from ft. to ft. Gage  
" Diam. from ft. to ft. Gage

## (7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Star  
Size of perforations 2 in. by 1/4 in.  
perforations from 162 ft. to 167 ft.  
perforations from ft. to ft.  
perforations from ft. to ft.  
perforations from ft. to ft.  
perforations from ft. to ft.

## (8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name  
Type Model No.  
Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

## (9) CONSTRUCTION:

Well seal—Material used in seal puddling clay  
Depth of seal 20 ft. Was a packer used? no  
Diameter of well bore to bottom of seal 9 in.  
Were any loose strata cemented off? ☐ Yes ☒ No Depth  
Was a drive shoe used? ☒ Yes ☐ No  
Was well gravel packed? ☐ Yes ☒ No Size of gravel:  
Gravel placed from ft. to ft.  
Did any strata contain unusable water? ☐ Yes ☐ No  
Type of water? depth of strata  
Method of sealing strata off

## (10) WATER LEVELS:

Static level 73 ft. below land surface Date 9-10-64  
Artesian pressure lbs. per square inch Date

## (11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 13 gal./min. with 0 ft. drawdown after 3 hrs.

Artesian flow g.p.m. Date

Temperature of water 54 Was a chemical analysis made? ☐ Yes ☒ No

## (12) WELL LOG:

Diameter of well below casing 6

Depth drilled 225 ft. Depth of completed well 225 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

| MATERIAL    | FROM | TO  |
|-------------|------|-----|
| Soil        | 0    | 2   |
| Blue clay   | 2    | 38  |
| Yellow "    | 38   | 81  |
| Blue "      | 81   | 102 |
| Yellow "    | 102  | 125 |
| Brown "     | 125  | 162 |
| Fine gravel | 162  | 167 |
| Brown clay  | 167  | 203 |
| Blue "      | 203  | 217 |
| Fine gravel | 217  | 225 |

Work started 8-25-1963 Completed 9-10-1964

Date well drilling machine moved off of well 9-12-1964

## (13) PUMP:

Manufacturer's Name Jacuzzi  
Type Submersible H.P. 3/4

## Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME (Person, firm or corporation) (Type or print)

Address

Drilling Machine Operator's License No. 207

[Signed] E.M. Gregory (Water Well Contractor)

Contractor's License No. 99 Date 10-10-1964

(USE ADDITIONAL SHEETS IF NECESSARY)