

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 1513E-35

State Permit No. 00820

(1) OWNER:

Name DENNIS OCHRIST
Address 16760 SE. STONEY BROOK CT. CLATSOP CO. OR 97015

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 300 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used TORCH

Size of perforations 1/8 in. by 10 in.
40 perforations from 240 ft. to 300 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "
" " " " " "
Bailer test 20 gal./min. with 22 ft. drawdown after 2 hrs.
Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT GROUT
Well sealed from land surface to 90 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 20 sacks
How was cement grout placed? PUT IN AS 8" STAFF PIPE WAS BEING REMOVED

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/4 -

Gravel placed from 300 ft. to 90 ft.

(10) LOCATION OF WELL:

County CLATSOP Driller's well number
1/4 1/4 Section 35 T. 15 R. 3-E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 292 ft.
Static level 213 ft. below land surface. Date 6/2/79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 0

Depth drilled 300 ft. Depth of completed well 300 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	2	0
CLAY RED	2	15	0
CLAY BROWN	15	83	0
ROCK SOLID BROWN	83	192	0
ROCK SOLID GREY	192	284	0
GRAVEL CEMENT	284	292	0
GRAVEL & COARSE SANDW.B.	292	296	213
GRAVEL CEMENT	296	300	213

RECEIVED

JUL 31 1979

WATER RESOURCES DEPT
SALEM, OREGON

Work started 5/11/79 Completed 6/2 1979

Date well drilling machine moved off of well 6/3 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Dennis Ochrist Date 6/10, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 246

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name LANZ Well Drilling
(Person, firm or corporation) (Type or print)

Address 15702 S. Neilbur Rd. Oregon City

[Signed] Donald H. Lanz
(Water Well Contractor)

Contractor's License No. 565 Date 6-10, 1979