

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

STATE ENGINEER

State Well No. 1/3-35 C

Permit No.

(1) OWNER:

Name OTIS COOK
Address RT 3 Box 749 GRESHAM OREGON

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 149' 4" ft. Gage 250"
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 61 ft. below land surface Date 1/18/68
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.
" " " "

Bailer test 18 gal./min. with 68 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water 56° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used CEMENT
Depth of seal 139 ft.
Diameter of well bore to bottom of seal 8 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☒ Yes ☐ No
Type of water? Iron depth of strata 110' to 130'
Method of sealing strata off CEMENT
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County CLACKAMAS Driller's well number 46
NE 1/4 NW 1/4 Section 35 T. 15 R. 3E W.M.
Bearing and distance from section or subdivision corner

379 SUNSHINE VLY. ORCH. TR.

(12) WELL LOG:

Diameter of well below casing

Depth drilled 152 ft. Depth of completed well 148 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
TOP SOIL	0	2	—
BROWN CLAY	2	30	—
RED CLAY	30	53	—
SOFT BLACK ROCK	53	113	45
HARD GRAY ROCK	113	118	45
SOFT GRAY ROCK	118	134	45
BROWN CLAY	134	137	—
CEMENTED GRAVEL	137	140	—
LOOSE GRAVEL	140	148	—
(WATER BEARING)	148	150	61
LOOSE GRAVEL	150	152	—

Work started 1/2 19 68 Completed 1/18 19 68

Date well drilling machine moved off of well 1/18 19 68

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] O. Kelle Date 1/18, 19 68
(Drilling Machine Operator)

Drilling Machine Operator's License No. 329

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Keller Well Drilling Co.
(Person, firm or corporation) (Type or print)

Address 16306 S.E. FRANKLIN, PORTLAND

[Signed] O. Kelle
(Water Well Contractor)

Contractor's License No. 462 Date 1/18, 19 68