

35/1W-3600

9809C 10/86

0A10

2872 0

RECEIVED

DEC 1891

"START CARD"

NOTICE OF BEGINNING OF WELL CONSTRUCTION
(as required by ORS 537.762)

DEC -4 1987

WATER RESOURCES DEPT.
SALEM, OREGON

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and
Mailing Address

Oki Nursery Co.

PO Box 115

Aurora, OR 97002

Proposed Commencement Date

12/2/87

Proposed Well Depth and Use:

250

Diameter

8

☐ Domestic☐ Community☐ Industrial☒ Irrigation☐ Thermal☐ Injection☐ Other

Proposed Well Location:

County

Clackamas

Township

3S

(N or S)

Range

1W

(E or W)

Section

36

At least 2
of these
must be
provided

1. SW 1/4 of SW 1/4 of above section

2. street address of
well location23788 NE Airport Rd
Aurora OR 97002

3. tax lot number of well location

4. attach approved map with location identified.
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

X

Owner's Signature

X

Bonded Water Well Constructor

Title

License No.

649

Company

Schneider Drilling Co.

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.

RECEIVED

CLAC 8792 XCW

35/1W-36cc

SEP 14 1987

WATER RESOURCES DEPT
SALEM, OREGON OK1 Nursery
Well Log

0	2	Top soil
2	16	Clay, silty, brown, med
16	18	Clay, brown, soft
18	42	Sand, brown, course & pea gravel
42	48	Gravel 1/2" minus w/black sand, med-fine
48	56	Sand, black, med-fine
56	60	Sand, brown, med-fine
60	62	Clay, grey, med-soft
62	64	Sand, grey, med-fine
64	70	Clay, grey, med-soft
70	79	Sand, black & brown, med
79	84	Clay, grey, med-soft
84	92	Clay, grey, med-soft, little silty
92	96	Sand, black, fine
96	110	Clay, grey, soft, little silty
110	112	Clay, grey, sandy, little gravel 1"
112	121	Sand, multi-colored med, little pea gravel
121	129	Gravel 1" minus, little sand, med
129	140	Gravel 2" minus, med, black sand, cemented
140	150	Sand, black, med, little pea gravel
150	155	Clay, grey, sandy, med-soft
155	158	Clay, grey, med
158	167	Clay, blue-green, med
167	169	Clay, grey, little sand, med-soft
169	179	Sand, multi-colored, med
179	190	Clay, silty, grey, med, little wood
190	192	Sand, multi-colored, med-fine
192	197	Clay, grey, sandy, med
197	200	Sand, cemented, multi-colored
200	202	Clay, grey, med-soft
202	212	Gravel 2" minus, multi-colored, med, sand
212	214	Clay, grey, sandy, med-soft
214	226	Cemented gravel 1-1/2" minus, sand, med
226	234	Sand, multi-colored, med, little clay
234	238	Sand, multi-colored, med, clay & pea gravel, little wood
238	241	Sand, multi-colored, med-course & pea gravel
241	249	Sand, cemented & gravel 3/4" minus, w/wood
249	264	Clay, grey, med

W0020.OKI