

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

STATE ENGINEER
SALEM, OREGON

State Well No.

State Permit No.

3S/1E-8 6

(1) OWNER:

Name E. C Meek Jr.
Address 4970 SW Hewett Blvd.
Portland, Oregon 97221

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

10" Diam. from 0 ft. to 58 ft. Gage 25
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used
Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 60 gal./min. with 316 ft. drawdown after 1 hrs.
37 " 239 " 1 "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement and Bentonite
Well sealed from land surface to 58 ft.
Diameter of well bore to bottom of seal 15 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 6 sacks
Number of sacks of bentonite used in well seal 3 sacks
Brand name of bentonite National
Number of pounds of bentonite per 100 gallons
of water 100 lbs./100 gals.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 68-73
1/4 NW 1/4 Section 8 T. 3S R. 1E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 218 ft.
Static level 59 ft. below land surface. Date 12-19-73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10
Depth drilled 380 ft. Depth of completed well 380 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown clay	0	34	
Muliyi-colored decomposed basalt	34	53	
Black basalt	53	114	
Red basalt	114	116	
Multi-colored basalt	116	131	
grey basalt	131	162	
Multi-colored basalt	162	174	
Black basalt, creveased	174	208	
Grey basalt hard	208	236	59
Grey basalt creveased, soft	236	240	
	240	254	
Black Basalt	254	264	
Black basalt, creased, hard	264	280	
Black basalt, crevesed, soft	280	339	
Black basalt, bad creaveased hard	339	380	59

Work started 11-23 1973 Completed 12-19 1973
Date well drilling machine moved off of well 12-19 1973

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Forrest L. Lewis Date 12-21, 1973
(Drilling Machine Operator)

Drilling Machine Operator's License No. 673

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Skyles Drilling and Supply
(Person, firm or corporation) (Type or print)

Address 1169 Molalla Avenue, Oregon City

[Signed] Marvin O. Skyles
(Water Well Contractor)

Contractor's License No. 553 Date 12-21, 1973

(USE ADDITIONAL SHEETS IF NECESSARY)

SP*45656-119