

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

# WATER WELL REPORT

STATE OF OREGON  
(Please type or print)

(Do not write above this line)

CLAC  
009165

State Well No. 3s/1E-12 ba

State Permit No. \_\_\_\_\_

## (1) OWNER:

Name Howard E. Parsell  
Address 11045 S. Beutel Rd.  
Oregon City, Oregon 97045

## (2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

## (3) TYPE OF WELL:

Rotary ☒ Driven ☐  
Cable ☐ Jetted ☐  
D ☐ Bored ☐

## (4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐  
Irrigation ☐ Test Well ☐ Other ☐

## (5) CASING INSTALLED:

6 " Diam. from 0 ft. to 108 ft. Gage 250  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_

## (6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used \_\_\_\_\_

| Size of perforations          | in.   | by    | in.       |
|-------------------------------|-------|-------|-----------|
| _____ perforations from _____ | _____ | _____ | _____ ft. |
| _____ perforations from _____ | _____ | _____ | _____ ft. |
| _____ perforations from _____ | _____ | _____ | _____ ft. |

## (7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name \_\_\_\_\_  
Type \_\_\_\_\_ Model No. \_\_\_\_\_  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

## (8) WELL TESTS:

Drawdown is amount water level is  
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?  
20 gal./min. with total ft. drawdown after 1 hrs.  
air rotary " " " "

Bailer test \_\_\_\_\_ gal./min. with \_\_\_\_\_ ft. drawdown after \_\_\_\_\_ hrs.

\_\_\_\_\_ gal. flow \_\_\_\_\_ g.p.m.

Temperature of water \_\_\_\_\_ Depth artesian flow encountered \_\_\_\_\_ ft.

## (9) CONSTRUCTION:

Well seal—Material used cement  
Well sealed from land surface to 20 ft.  
Diameter of well bore to bottom of seal 10 in.  
Diameter of well bore below seal 6 in.  
Number of sacks of cement used in well seal 15 sacks  
How was cement grout placed? pressure grouted

Was a drive shoe used? ☒ Yes ☐ No Plugs \_\_\_\_\_ Size: location \_\_\_\_\_ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? \_\_\_\_\_ depth of strata \_\_\_\_\_

Method of sealing strata off \_\_\_\_\_

Was well gravel packed? ☐ Yes ☒ No — Size of gravel: \_\_\_\_\_

Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

## (10) LOCATION OF WELL:

County Clackamas Driller's well number D 289-80  
NE  $\frac{1}{4}$  NW  $\frac{1}{4}$  Section 12 T. 3S R. 1E W.M.  
Bearing and distance from section or subdivision corner  
Beutel Road

## (11) WATER LEVEL: Completed well.

Depth at which water was first found 46 ft.  
Static level 18 ft. below land surface. Date 4/2/80  
Artesian pressure \_\_\_\_\_ lbs. per square inch. Date \_\_\_\_\_

## (12) WELL LOG:

Diameter of well below casing 6

Depth drilled 140 ft. Depth of completed well 140 ft.

Formation: Describe color, texture, grain size and structure of materials;  
and show thickness and nature of each stratum and aquifer penetrated,  
with at least one entry for each change of formation. Report each change in  
position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL               | From | To  | SWL |
|------------------------|------|-----|-----|
| topsoil brown          | 0    | 2   |     |
| clay brown sticky      | 2    | 31  |     |
| clay with gravel       | 31   | 35  |     |
| clay brown             | 35   | 46  |     |
| sandstone yellow       | 46   | 65  |     |
| sand yellow            | 65   | 100 |     |
| sandstone brown/yellow |      |     |     |
| water/bear             | 100  | 123 | 18  |
| clay yellow            | 123  | 140 |     |

RECEIVED

APR 4 1980

WATER RESOURCES DEPT  
SALEM, OREGON

Work started 4/1/80 19 Completed 4/2/80 19  
Date well drilling machine moved off of well 4/2/80 19

## Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.  
Materials used and information reported above are true to my  
best knowledge and belief.

[Signed] Walter Mace Date 4/2, 1980  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 595

## Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is  
true to the best of my knowledge and belief.

Name S & M Drilling  
(Person, firm or corporation) (Type or print)

Address 399 S E Walnut Canby, Ore. 97013

[Signed] Walter Mace  
(Water Well Contractor)

Contractor's License No. 497 Date 4/2/80, 1980