

RECEIVED

JUL 22 1966 WATER WELL REPORT



NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 STATE ENGINEER STATE OF OREGON within 30 days from the date of well completion. SALEM OREGON (Please type or print)

State Well No. 3/1-21 State Permit No.

(1) OWNER:

Name CARRIGG, John Address 200 N. W. Virginia Canby, Oregon

(2) LOCATION OF WELL:

County Clackamas Driller's well number 1966-22 1/4 Section 5521 T. 3S R. 1E W.M. Bearing and distance from section or subdivision corner Lot 6 of Olivers' Addition

(3) TYPE OF WORK (check):

Well [checked] Deepening [ ] Reconditioning [ ] Abandon [ ] Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic [checked] Industrial [ ] Municipal [ ] Irrigation [ ] Test Well [ ] Other [ ] Rotary [checked] Cable [ ] Dug [ ] Driven [ ] Jetted [ ] Bored [ ]

(6) CASING INSTALLED:

6" Diam. from 0 ft. to 140 ft. Gage .025 Threaded [ ] Welded [ ]

(7) PERFORATIONS:

Perforated? [ ] Yes [checked] No [ ] Type of perforator used Size of perforations in. by in. perforations from ft. to ft.

(8) SCREENS:

Well screen installed? [ ] Yes [checked] No [ ] Manufacturer's Name Model No. Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal-Material used in seal Benbante Depth of seal 20 ft. Was a packer used? [checked] Diameter of well bore to bottom of seal 10 in. Were any loose strata cemented off? [ ] Yes [checked] No [ ] Depth Was a drive shoe used? [checked] Yes [ ] No [ ] Was well gravel packed? [ ] Yes [checked] No [ ] Size of gravel: Gravel placed from ft. to ft. Did any strata contain unusable water? [ ] Yes [checked] No [ ] Type of water depth of strata Method of sealing strata off

(10) WATER LEVELS:

Static level 90 ft. below land surface Date July 6/66 Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level Was a pump test made? [ ] Yes [checked] No [ ] If yes, by whom? Yield: gal./min. with ft. drawdown after hrs. Bailer test 30 gal./min. with 35 ft. drawdown after / hrs. Artesian flow g.p.m. Date Temperature of water Was a chemical analysis made? [ ] Yes [checked] No [ ]

(12) WELL LOG:

Diameter of well below casing 6. Depth drilled 145 ft. Depth of completed well 141 ft. Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with columns: MATERIAL, FROM, TO. Rows include: Top soil (0-3), clay gravel Brown (3-12), gravel (12-18), clay Brown (18-60), coarse sand (60-98), clay green (98-133), sand fine (133-139), clay green (139-140), sand coarse (water) (140-143), clay-green (143-145).

Work started June 20 19 66 Completed July 8 19 66 Date well drilling machine moved off of well July 8 19 66

(13) PUMP:

Manufacturer's Name Fairbanks-Morse Type: Submersible H.P. 5

Water Well Contractor's Certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. NAME SKYLES DRILLING & SUPPLY (Person, firm or corporation) (Type or print) Address GLADSTONE, OREGON Drilling Machine Operator's License No. [ ] [Signed] George H. Skyles (Water Well Contractor) Contractor's License No. 58 Date July 18 19 66



Oregon Water Resources Department  
 725 Summer Street NE, Suite A  
 Salem Oregon 97301  
 (503) 986-0900  
 www.oregon.gov/owrd

# Application for Well ID Number

RECEIVED

SEPT 22 2021

Do not complete if the well already has a Well Identification Number.

**I. OWNER INFORMATION**

OWRD

Current Owner Name (please print): John E and Eileen E Carrigg Trust  
 Mailing Address: PO Box 261  
 City, State, Zip: Canby  
 Mail Well ID to:  SAME AS ABOVE  In Care Of (C/O)  
 Name & Address: Kathleen Cutsforth, trustee  
 City, State, Zip: PO Box 261, Canby, OR 97013

**II. WELL LOCATION INFORMATION** (Please fill out as completely as possible)

Township: 3 (North / South) Range: 1 (East / West) Section: 21 SE 1/4 of the SW 1/4  
 Tax Lot (usually last 3-5 numbers of Tax Map #): 1600 County Clackamas  
 GPS Coordinates: 45.28879668; -122.69641263 per WR App Map  
 Street Address of Well, City: NW 31st Ave + N Holly St (NE corner)  
 If the property had a different street address in the past: \_\_\_\_\_

**III. GENERAL WELL INFORMATION** (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation  
 Date Well Constructed (or property built): 7-8-1966 Total Well Depth: 141 ft Casing Diameter: 6"  
 Owner at time the well was constructed (if known): John Carrigg Well Report # (if known): CLAC 9477  
 Other Information: Irrigation WR permit # G 17492

SUBMITTED BY (please print): Kathe Cutsforth  
 PHONE: 503 936 9629 EMAIL &/or FAX: Johns.dolter@protonmail.com  
Kathecutsforth@gmail.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301, fax to (503) 986-0902, or you are welcome to email the completed form to Ladeena.K.Ashley@oregon.gov.

For Official Use Only by the Oregon Water Resources Department:

Received Date:  
9-22-21

Well Report Number:  
CLAC 9477

Well Identification #:  
L-144433