

WATER WELL REPORT

STATE OF OREGON

RECEIVED

NOV 5 1980

WATER RESOURCES DEPT
SALEM, OREGON

State Well No. 35/1E-2506

State Permit No.

(1) OWNER:

Name Gary N Falkenberg
 Address 22036 S Central Pt Rd
 City Oregon City State Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Any Air ☐ Driven ☐
 Dry Mud ☐ Dug ☐
 e ☒ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
 Irrigation ☐ Test Well ☐ Other ☐
 Thermal: Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
 Threaded ☐ Welded ☒

" Diam. from 0 ft. to 2.45 ft. Gauge 2.50

" Diam. from _____ ft. to _____ ft. Gauge _____

LINER INSTALLED:

" Diam. from _____ ft. to _____ ft. Gauge _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used _____

Size of perforations _____ in. by _____ in.

_____ perforations from _____ ft. to _____ ft.

_____ perforations from _____ ft. to _____ ft.

_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot Size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot Size _____ Set from _____ ft. to _____ ft.

WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☒ Yes ☐ No If yes, by whom? Driller

Yield: 30 gal./min. with 71 ft. drawdown after 5 hrs.

" " " " " "

test _____ gal./min. with drill stem at _____ ft. hrs.

er test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered 2.48 ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 2.4 ft.

Diameter of well bore to bottom of seal 9.7 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 8 sacks

How was cement grout placed? Poured

Was pump installed? Yes Type Suck HP 1.5 Depth 126 ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☒ Yes ☐ No

Type of Water? Fine Sand depth of strata 121

Method of sealing strata off Piped

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/4" #30

Gravel placed from 2.45 ft. to 2.60 ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number _____

NW 1/4 SW 1/4 Section 25 T. 33 R. 1E W.M.

Tax Lot # _____ Lot _____ Blk _____ Subdivision _____

Address at well location: 223 23 S Central Pt Rd

Oregon City Ore

(11) WATER LEVEL: Completed well.

Depth at which water was first found 246 ft.

Static level 54 ft. below land surface. Date 10-17-80

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 260 ft. Depth of completed well 260 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	2	
Brown Clay	2	16	
Brown Silty Clay	16	20	
Brown Clay	20	40	
Brown sand	40	62	
Brown clay with gravel	62	74	
Blue Clay	74	121	
Fine Gray sand	121	124	40
Green Clay	124	134	
Blue Clay	134	180	
Gray Silty Clay	180	246	
Green sand stone	146	156	
lvs	156	158	
Basalt	158	160	

Work started 10-8 19 80 Completed 10-18 19 80

Date well drilling machine moved off of well 10-18 19 80

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

(Signed) John W. Beck Date 10-18 19 80
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 437

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name John W. Beck Well Drilling
 (Person, firm or corporation) (Type or print)

Address 24137 99th Lane Dr. Comp Co.

(Signed) John W. Beck
 (Water Well Contractor)

Contractor's License No. 449 Date 10-18 19 80

NOTICE TO WATER WELL CONTRACTOR

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310

SP*12658-090

within 30 days of date of well completion