

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97301
within 30 days from the date
of well completion.

RECEIVED

STATE OF OREGON
(Please type or print)

(Do not write above this line)

SEP 14 1977

State Well No. 35/E-26

State Permit No.

(1) OWNER:

Name **Robert Milner** WATER RESOURCES DEPT.
SALEM, OREGON

Address **Canby, OR 97013**
22901 S Haines Rd

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6 5/8 OD " Diam. from 0 ft. to 9 1/4 ft. Gage .250

5 ID-PVC " Diam. from 90 ft. to 160 ft. Gage 125 lb.
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used **cutting torch & skill saw**

Size of perforations **1/4** in. by **10** in.
10 perforations from 75 ft. to 88 ft.
24 perforations from 92 ft. to 158 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test **12** gal./min. with **15** ft. drawdown after **1** hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used **cement**

Well sealed from land surface to **23** ft.

Diameter of well bore to bottom of seal **10** in.

Diameter of well bore below seal **8"** in.

Number of sacks of cement used in well seal **4** sacks

Number of sacks of bentonite used in well seal **0** sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County **Clackamas** Driller's well number

1/4 1/4 Section **26** T. **3S** R. **1E** W.M.

Bearing and distance from section or subdivision corner **CBB**

(11) WATER LEVEL: Completed well.

Depth at which water was first found **80** ft.

Static level **65** ft. below land surface. Date **8-19-77**

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing **6"**

Depth drilled **160** ft. Depth of completed well **160** ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Clay	0	5	
sand	5	22	
gravel & boulders dry	22	30	
dry gravel-some small boulders	30	68	
gravel (wet)	68	90	
brown clay	90	93	
blue clay	93	111	
hard brown packed sand	111	114	
blue clay	114	126	
small gravel & sand silt	126	140	
fine sand silt	140	153	
blue clay	153	160	65 ft

Work started **8-8** 19 **77** Completed **8-19** 19 **77**

Date well drilling machine moved off of well **8-22** 19 **77**

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] **John R. Meeker** 8-20 1977
(Drilling Machine Operator)

Drilling Machine Operator's License No. **50**

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name **JOHN MEEKER WELL DRILLING**
(Person, firm or corporation) (Type or print)

Address **2902 Portland Rd, Newberg, OR 97132**

[Signed] **John R. Meeker**
(Water Well Contractor)

Contractor's License No. **111** Date **8-20** 19 **77**