

STATE OF OREGON
WATER WELL REPORT WATER RESOURCES DEPT.
(as required by ORS 537.765) SALEM, OREGON

JUL 01 1991

CLAS
9811

4S/4E/4 CC

(START CARD) # 24841

(1) OWNER: Well Number: _____
Name Cheryl Alexander & Vicki McKee
Address 26046 S. Wallens Rd.
City Estacada State OR Zip 97023

(2) TYPE OF WORK:
☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes ☐ No ☒ Depth of Completed Well 122 ft.
Explosives used Yes ☐ No ☒ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	27	Cement	27	0	22
8"	27	127				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 127 ft. to 27 ft. Size of gravel per

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
6"	18"	87'	16CL	☐	☒	☐	☐
6"	87'	127'	20CL	☐	☒	☐	☐

Liner: _____

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
☒ Perforations Method SAW
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
87'	127'	1/8x8	42	6'		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing
Yield gal/min 100 Drawdown 15' Drill stem at _____ Time 2 hrs.

Temperature of water 53 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☒ Other shallow
Depth of strata: 21

(9) LOCATION OF WELL by legal description:
County Clackamas Latitude _____ Longitude _____
Township 4S N or S, Range 4E E or W, WM.
Section 4 SW 1/4 SW 1/4
Tax Lot 2600 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) SAW

(10) STATIC WATER LEVEL:
28 ft. below land surface. Date 6-19-91
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 21

From	To	Estimated Flow Rate	SWL
17	21	6 1/2	10'
105	120	100 +	28'

(12) WELL LOG: Ground elevation 1100

Material	From	To	SWL
Topsoil	0	1	
Clay - Red	1	17	
Decomposed RK & gravel	17	21	10'
Clay - Brown	21	37	
Decomposed RK	37	105	
Sand & Gravel	105	120	28'
Clay - Lt. Brown	120	125	

Date started May 13-91 Completed 6-22-91

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Richard Youngberg WWC Number 1515
Date 6-22-91

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed W.O. Youngberg WWC Number 251
Date 6-25-91