

CLAC

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97301
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

CLAC
00989

State Well No. 114-29

State Permit No.

RECEIVED
SEP 30 1969
STATE ENGINEER
SALEM, OREGON

(1) OWNER:

Name Hank Nappe
Address 1200 SE Roberts
Clatskanie, Oreg.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 510 ft. Gage 250
5 1/4" Diam. from 209 ft. to 257 ft. Gage 100
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills Knife Torch
Size of perforations 3/16 in. by 3 in. cut time
260 perforations from 140 ft. to 209 ft.
110 perforations from 211 ft. to 257 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 120 ft. below land surface Date Sept 25
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom? driller.
60 gal./min. with 9 ft. drawdown after 1 hrs.
75 " 12 " 1 "
90 " 16 " 7 "
Bailer test 30 gal./min. with 8 ft. drawdown after 1 hrs.
Artesian flow no g.p.m. Date

Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cemented at 120'
Depth of seal 120' backfill clay slurry
Diameter of well bore to bottom of seal 8 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Clatskanie Driller's well number
1/4 1/4 Section 29 T. 13 R. 4E W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing to bottom
Depth drilled 257 ft. Depth of completed well 257 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	
red clay	2	30	
yellow buff	30	42	
clay & cobbles	42	56	
boulders	56	80	
cement gravel	80	132	
loosely cemented	132	140	
cement gravel	140	226	
loose streak	226	230	
cement gravel	230	240	
brown sand & rock	240	257	

Work started Aug 19 1969 Completed Sept 25 1969
Date well drilling machine moved off of well Sept 25 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Remy Norme Date Sept 26 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 215

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME A. O. Olson
(Person, firm or corporation) (Type or print)

Address 18211 SE Powell

[Signed] A. O. Olson
(Water Well Contractor)

Contractor's License No. 282 Date Sept 29 1969