

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

STATE ENGINEER

SALEM OREGON 65391

STATE ENGINEER

SALEM, OREGON

State Permit No.

State Well No.

CLAC 00992

1/4-29caab

(1) OWNER:

Name

Address

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 176 ft. Gage 277
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used

Size of perforations

3/16 in. by

3 in.

300 perforations from 140 ft. to 170 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 135 ft. below land surface Date Feb-68

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

125 gal./min. with 30 ft. drawdown after 6 hrs.

" " "

" " "

Bailer test 20 gal./min. with 2 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION: cement sand,

Well seal—Material used backfill clay slurry

Depth of seal 95 ft.

Diameter of well bore to bottom of seal 10 in.

Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Clackamas Driller's well number

1/4 1/4 Section 29 T. 15 R. 4E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 178 ft. Depth of completed well 178 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	
red clay	2	28	
yellow loess	28	65	
clay & cobbles	65	82	
lava rock	82	86	
clay & cement	86	135	
loosely cemented	135	150	
water bearing gravel	150	170	
loose gravel with water	150	170	
Heavy water bearing	170	178	

10" surface pipe set to 83'

Work started Feb 1968 Completed Feb 1968

Date well drilling machine moved off of well Feb 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Henry W. W. Date March 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME H.O. Olson
(Person, firm or corporation) (Type or print)

Address 18211 SE Powell Street,resham,

[Signed] H.O. Olson
(Water Well Contractor)

Contractor's License No. 282 Date March 1968