

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT.

SALEM, OREGON 97310

within 30 days from the date

of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

WATER RESOURCES DEPT.

SALEM, OREGON

State Well No.

State Permit No.

DEC 21 1978

8N/7W-30cb

(1) OWNER:

Name Peter Gallucci
Address 3621 SE FRANKLIN
PORTLAND ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 58 ft. Gage 350

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" 59gpm High Pressure Air Test

" " " "

Puller test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement Grout
Well sealed from land surface to 58 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 30 sacks
How was cement grout placed? Pumped

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clatsop Driller's well number
NW 1/4 SW 1/4 Section 30 T. 8 R. 7W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 350 ft.

Static level 54 ft. below land surface. Date 8-30-78

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 428 ft. Depth of completed well 428 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
EARTH	0	3	
SAND & GRAVEL COARSE	3	8	
COBBLES	8	13	
SANDSTONE TAN	13	20	
CLAY & Pebbles Brown	20	40	
" " GREEN	40	45	
SAND Black Fine	45	51	
GRAVEL	51	55	
CLAY GREEN	55	60	
" " Grey	60	350	
Rock Grey Soft	350	355	W 8
CLAY Grey	355	375	
Rock Grey Med	375	398	
CLAY stone Grey	398	428	54

Work started 8-21 1978 Completed 8-30 1978

Date well drilling machine moved off of well 8-30 1978

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Date, 19.....
(Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name McKnight Well Drilling
(Person, firm or corporation) (Type or print)

Address Pl. 3 Box 3054 WARRENORE

[Signed] for McKnight 97053
(Water Well Contractor)

Contractor's License No. 576 Date 10-4, 1978