

JAN 2 1987

STATE OF OREGON
WATER WELL REPORT WATER RESOURCES DEPT.
(as required by ORS 537.765) SALEM, OREGON

COLU

1962

7N/2W-20

(1) OWNER: Owner's Well Number: 4
Name Leo Deal (Western Hills Mobile Court)
Address 74866 Ocean Rd.
City Rainier State ORE. Zip 97048

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other

(5) BORE HOLE CONSTRUCTION:
Depth of Completed Well 225 ft.
Special Standards date of approval _____

HOLE Diameter	From	To	SEAL Material	From	To	Amount sacks or pounds
10"	0	43	Cement	0	43	19 sacks
6"	43	205				

How was seal placed? Method A B C D E
 Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	11	45	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4 1/2"	25	225	160	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

Perforations Method Saw
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
160	205	1/4"	60	4"		<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailer Air Flowing 3 M
 Artesian

Yield gal/min	Pumping level	Drill stem at	Time
22		224	1 hr

Temperature of water 49° Depth Artesian Flow Found 75-155
Was a water analysis done? Yes By whom JA
Did any strata contain water not suitable for intended use? Too little NO
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Columbia Latitude _____ Longitude _____
Township 7 N or S, Range 2 or W, WM.
Section 20 Lot 7220-030 Block 00380 Subdivision _____
Tax Lot _____
Street Address of Well (or nearest address) 74227 Frank Hill Rd., Rainier, Oregon 97048

(10) STATIC WATER LEVEL:
_____ ft. below land surface. Date 11-26-86
Artesian pressure 2 lb. per square inch. Date 11-26-86

(11) WELL LOG: Ground elevation 500'

Material	From	To	WB?	SWL
TOP Soil	0	1		
Clay Gray	1	8		
Clay Gray	8	15	G	
Rock Brownish Gray	15	20	M	
Rock Blackish Gray	20	48		
Rock Brownish Black	48	55	5	0
Rock Blackish Gray	55	85	7	0
Rock Greenish Black	85	105	10	0
Rock Brownish Black	105	115	15	0
Rock Black	115	125	20	0
Rock Greenish Black	125	150	22	0
Rock Black	150	157	25	0
Rock Greyish Black	157	225	25	0

water bearing 75 to 155
overflows @ 3 GPM

Date started 11-24-86 Completed 11-26-86

(unbonded) Water Well Constructor Certification:
I constructed this well in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed IRA Bopp Date 11-26-86

(bonded) Water Well Constructor Certification:
I accept responsibility for construction of this well and its compliance with all Oregon water well standards. This report is true to the best of my knowledge and belief.
Signed IRA Bopp Date 11-26-86
Company IRA Bopp Well Drilling Co. Job No. 23