

The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER RESOURCES DEPT.

SALEM, OREGON

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

Do not write above this line)

State Well No.

State Permit No.

(1) OWNER:

Name Bill ScholtenAddress P.O. Box 938, Rainier, Oregon 97048

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒6" Diam. from 1 ft. to 40 ft. Gage 2505" Diam. from 33 ft. to 295 ft. Gage SDR-26

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.Type of perforator used DrilledSize of perforations 1/2 in. by Round in.

40 perforations from 160 ft. to 180 ft.

60 perforations from 255 ft. to 285 ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 10 gal./min. with 160 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 38 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 9 sacks

How was cement grout placed? Pressure PumpedWas a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Columbia Driller's well number

1/4 1/4 Section 8 T. 7 R. 3W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 170 ft.

Static level 130 ft. below land surface. Date 10/18/84

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 295 ft. Depth of completed well 295 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	2	
Clay, Yellow	2	14	
Shale, Blue	14	23	
Rock, Brown, Broken	23	33	
Rock, Blue Basalt, Hard	33	110	
Shale, Blue, Soft	110	138	
Rock, Blue, Soft	138	165	
Sandrock, Gray (2 GPM 170-180)	165	200	130
Shalerock, Brownish Gray	200	222	
Rock, Blue	222	240	
Shale, Brown	240	250	
Sandrock, Blue	250	261	
Sandstone, Blue (WaterBearing)	261	282	130
Sandrock, Gray, Med.	282	295	

Work started 10/16 1984 Completed 10/18 19 84

Date well drilling machine moved off of well 10/18 19 84

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Julie Williams Date 10/22, 1984
(Drilling Machine Operator)

Drilling Machine Operator's License No. 427

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Williams Well Drilling, Inc.

(Person, firm or corporation) (Type or print)

Address 957 Jackson Hwy. So., Toledo, Wa. 98591

[Signed] Julie Williams
(Water Well Contractor)

Contractor's License No. 589 Date 10/22, 1984